

**CERTIFIED RECORD OF LAND CORNER**

**History of original corner establishment:**

Corner was established by William R. Graddon, US Deputy Surveyor, during the original survey Contract No. 409 dated March, 1882.

"Set a post 3 ft. long, 3 ins square 24 ins in the ground, for 1/4 sec. cor., marked 1/4S on W. face, from which

A pine 20 ins diam. bears N65°E, 10 lks. dist., marked 1/4 S BT.

A pine 36 ins diam. bears S20°W, 59 lks. dist., marked 1/4 S BT."

**DIAGRAM**

**T10S R37E**

**1/4**

**S27**

**S26**

**1994**

**PLS699**

**Description of corner evidence found:**

Found two root holes that fit record bearing and distance and was near proportionate location.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

Set 2" aluminum pipe with 3 1/4" aluminum cap, stamped as shown in diagram, 28" in ground, from existing evidence, from which new accessories are:

A 12" Ponderosa Pine, bears N10°30'W, 15.9 ft., scribed "1/4 S27 BT"

A 14" Ponderosa Pine, bears N48°20'E, 12.5 ft., scribed "1/4 S26 BT"

A blue DEEP ( Underground Magnetic Locator ), bears S48°20'W, 3.5 ft. from corner position, 0.8 ft. in ground.

An orange DEEP, bears S10°30'E, 2.6 ft. from corner position, 0.9 ft. in ground.

I, Leland Lee Myers, 587 E Auburn Street, PO Box 98, Sumpter, OR 97877, do hereby certify that on November 19, 1994, I monumented the corner as herein described.

**FILED IN THE OFFICE OF THE BAKER COUNTY SURVEYOR THIS**  
**7 DAY OF Feb, 1995.**

10-37-67

**Baker County Surveyor**

Client: Lyle Defrees & US Forest Service



Renewal Date 1/1/97

**T10S R37E T-17**