

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

## History of original corner establishment:

William R. Grandon, U.S. Deputy Surveyor  
July 1, 1882

80.00 Set a granite stone 18 x 10 x 10 ins., 12 ins. in the ground, for the cor. to secs. 4,5,8 and 9., marked with 5 notches on S and 4 notches on E. edges, from which:

A pine, 44 ins. diam., bears N.40°E., 130 lks. dist., mkd. T10S R37E S4 BT.

A pine, 36 ins. diam., bears S.30°E., 139 lks. dist., mkd. T10S R37E S9 BT.

A pine, 36 ins. diam., bears S.70°W., 28 lks. dist., mkd. T10S R37E S8 BT.

A pine, 36 ins. diam., bears N.5°W., 64 lks. dist., mkd. T10S R37E S5 BT.

Owen C. Chatters, II and Lester E. Fisher, Cadastral Surveyors  
July 26, 1974

The cor. of secs. 4,5,8 and 9, determined at record bearing and distance from the remains of the original bearing trees:

A root hole, bears N.40°E., 130 lks. dist., with a down pine alongside, 50 ins. diam., with illegible scribe marks visible on open blaze.

A root hole, bears S.70°W., 28 lks. dist., with a down pine alongside, 36 ins. diam., with scribe marks T10S R37E S8 BT visible on open blaze.

A pine, 40 ins. diam., bears N.5°W., 64 lks. dist., mkd. T10S R37E S5 BT visible on partially open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

A ponderosa pine, 11 ins. diam., bears N.68°E., 60 lks. dist., mkd. T10S R37E S4 BT.

A ponderosa pine, 8 ins. diam., bears S.58°E., 76 lks. dist., mkd. T10S R 37E S9 BT.

A ponderosa pine, 10 ins. diam., bears S.65°W., 4 lks. dist., mkd. T10S R 37E S8 BT.

A ponderosa pine, 10 ins. diam., bears N.20°W., 121 lks. dist., mkd. T10S R 37E S5 BT.

Bury a granite stone, 15 x 9 x 7 ins., with an X chiseled on W. face, and deposit a glass bottle alongside iron post.

## Description of corner evidence found:

Found a 3" BLM brass cap, 0.5' above the ground with no stones, from which:

A pine, 34" diam., bears N.5°17'W., 42.9', scribe visible.

A pine, 14" diam., bears N.68°46'E., 38.9', with healed blaze.

A pine, 12" diam., bears S.59°43'E., 49.4', with healed blaze.

A pine, 13" diam., bears S.60°52'W., 3.2', with healed blaze and 60d nail with washer on side of tree "699"

Description of monument and accessories I established to perpetuate the original location of this corner:

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_ I hereby certify that the within instrument was filed in this office  
for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
by \_\_\_\_\_

(COUNTY OFFICIAL)

(DEPUTY)

E-9

DIAGRAM  
T 10 S R 37 E

S 5 | S 4

S 8 | S 9

1971

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*R. David Schurian* 7-15-74

OREGON  
JUNE 18, 1976  
R. DAVID SCHURIAN  
1060

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-82