

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

According to a plat filed at the Baker County Surveyors Office on June 29, 1994, survey number 10-37-37. Surveyed by Hanley Engineering for Evan Hale on April 2- June 15, 1994.

Set 5/8" x 30" rebar and plastic cap marked " HANLEY ENGRG PLS 1206"

DIAGRAM

1
NE --- S 8
16

RLS 1060
1995

Description of corner evidence found:

Found a 5/8" x 30" rebar with a yellow plastic cap, marked "HANLEY ENGR. PLS 1206".

Description of monument and accessories I established to perpetuate the original location of this corner:

At rebar position, set a USFS 3 1/4" aluminum capped monument 18" in the ground, with a mound of stone to cap, rebar set inside the pipe, from which:

A pine, 9" in diam., bears N.31°30'E., 26.4 ft., double blazed and scribed "NE1/16S8BT" with nail and brass washer "RLS 1060", on face of blaze.

A pine, 7" in diam., bears S.12°30'E., 22.2 ft., double blazed and scribed "NE1/16S8BT" with nail and brass washer "RLS 1060", on face of blaze.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

F-8

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-83