

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
July 1, 1882

80.00 Set a basalt stone 14 x 9 x 8 ins., 9 ins. in the ground, for the cor. to secs. 7,8,17 and 18, marked with 4 notches on S and 5 notches on E. edges, from which:

A pine, 30 ins. diam., bears N.75°E., 40 lks. dist., mkd. T10S R37E S8 BT.

A pine, 18 ins. diam., bears S.17°E., 47 lks. dist., mkd. T10S R 37E S17 BT.

A pine, 14 ins. diam., bears S.20°W., 84 lks. dist., mkd. T10S R 37E S18 BT.

A pine, 16 ins. diam., bears N.68°W., 50 lks. dist., mkd. T10S R 37E S7 BT.

DIAGRAM
T 10 S R 37 E

S 7 | S 8

S 18 | S 17

1971

Owen C. Chatters, II and Lester E., Fisher, Cadastral Surveyors
July 26, 1974

The cor. of secs. 7,8,17, and 18, determined at record bearing and distance from the remains of the original bearing trees:

A pine, 36 ins. diam., bears N.75°E., 40 lks. dist., with scribe marks T10S R 37E S8 BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

A ponderosa pine, 12 ins. diam., bears N.21°E., 39½ lks. dist., mkd. T10S R 37E S8 BT.

A ponderosa pine, 15 ins. diam., bears S.21°W., 217 lks. dist., mkd. T10S R 37E S18 BT.

A ponderosa pine, 11 ins. diam., bears N.10°W., 115 lks. dist., mkd. T10S R 37E S7 BT.

No other trees available within limits.

Bury a basalt stone, 10 x 7 x 4 ins., with an X chiseled on W. face, alongside iron post, and raise a mound of stone, 2 ft. base, 1½ ft. high, W. of the corner.

The corner is located 54 lks. south of a fence, extending N.45°W. and S.45°E.

Description of corner evidence found:

Found a 2½" BLM brass cap, 4" out of the ground, in a mound of stone, from which:

A pine, 17" diam., bears N.12°43'W., 75.6', scribed "T10SR37ES8BT".

A pine snag, 25" diam., bears N.70°10'W., 33.1', scribed "T10SR37ES7BT".

A pine, 36" diam., bears N.75°28'E., 26.4', scribed "T10SR37ES7BT".

A pine, 21" diam., bears S.13°35'E., 31.4', scribed "T10SR37ES17BT".

Description of monument and accessories I established to perpetuate the original location of this corner:

A fir, 8" in diam., bears S.71°W., 39.7 ft., double blazed and scribed "T10SR37ES18BT" with nail and brass washer "RLS 1060", on face of blaze.

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060