

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
July 1, 1882

39.81 Set a basalt stone 12 x 10 x 5 ins., 8 ins. in the ground, for the
¼ sec. cor. marked ¼ on N. face, from which:

A tamarack, 24 ins. diam., bears N.50°E., 7 lks. dist., mkd.
¼SBT.

A fir, 36 ins. diam., bears S.80°W., 15 lks. dist., mkd. ¼SBT.

DIAGRAM
T 10 S R 37 E
S 8
¼-----
S 17

1971

Owen C. Chatters, II and Lester E., Fisher, Cadastral Surveyors
July 26, 1974

The ¼ sec. cor. of secs. 8 and 17, determined at record bearing and distance from the remains
of the original bearing trees:

A western larch stump, 24 ins. diam., bears N.63°E., 7 lks. dist., mkd. ¼SBT visible on
open blaze(record, N.50°E.).

A fir stump, 48 ins. diam., bears S.80°W., 15 lks. dist., mkd. BT visible on open blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap, from which
new bearing trees:

A white fir, 14 ins. diam., bears N.39°E., 26 lks. dist., mkd. ¼ S8 BT.

A ponderosa pine, 10 ins. diam., bears S.41°W., 60 lks. dist., mkd. ¼ S17 BT.

Bury a granite stone, 15 x 6 x 3 ins., with an X chiseled on N. face, alongside iron post,

Description of corner evidence found:

Found a 3" BLM brass cap, flush with the ground, from which:

A stump, 15" diam., bears N.59°20'E., 5.7', scribed "¼SBT".

A fir, 18" diam., bears N.35°30'E., 17.4', scribe visible.

A pine, 11" diam., bears S.38°22'W., 39.2', with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

A 5/8" x 18" rebar, with an 2 1/2" aluminum cap, marked "T10S R37E S17 RM RLS 1060,
with an arrow pointing to the monument", bears S.15°05'E., 19.2'

A 5/8" x 18" rebar, with an 2 1/2" aluminum cap, marked " T10S R37E S17 RM RLS
1060, with an arrow pointing to the monument", bears S.71°42'E., 13.7'.

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060