

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
July 1, 1882

80.00 Set a basalt stone 3x11x8 ins. 9 ins in the ground for cor. to secs. 8,9,16, and 17 marked with 4 notches on S and E. edges from which:

- A pine, 18 ins. diam., bears N.45°E., 47 lks. dist., mkd. T10S R37E S9 BT.
- A pine, 30 ins. diam., bears S.65°E., 100 lks. dist., mkd. T10S R37E S16 BT.
- A pine, 10 ins. diam., bears S.15°W., 38 lks. dist., mkd. T10S R37E S17 BT.
- A pine, 22 ins. diam., bears N.30°W., 29 lks. dist., mkd. T10S R37E S8 BT.

DIAGRAM
T 10 S R 37 E

S 8 | S 9

S 17 | S 16

1971

Owen C. Chatters, II and Lester E., Fisher, Cadastral Surveyors
July 26, 1974

The cor. of secs. 8,9,16 and 17, monumented with the original basalt stone, 10 x 6 x 5 ins., firmly set 6 ins. in the ground, mkd. with faint chisel marks on S. and E. faces, from which remains of original bearing trees:

- A pine, 18 ins. diam., bears N.45°E., 47 lks. dist., mkd. T10S R37E S9 BT visible on open blaze.
- A pine stump, 30 ins. diam., bears S.65°E., 100 lks. dist., no marks visible on partial blaze.
- A pine stump, 12 ins. diam., bears S.15°W., 38 lks. dist., no marks visible on partial blaze.

At the corner point

Set an iron post, 28 ins. long, 2½ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

- A fir, 6 ins. diam., bears N.42°E., 27 lks. dist., mkd. T10S R37E S9 BT.
- A ponderosa pine, 7 ins. diam., bears S.72°E., 80 lks. dist., mkd. T10S R37E S16 BT.
- A ponderosa pine, 9 ins. diam., bears S.35°W., 97 lks. dist., mkd. T10S R37E S17 BT.
- A ponderosa pine, 16 ins. diam., bears N.85°W., 34 lks. dist., mkd. T10S R37E S8 BT.

Bury corner stone to which I add an X chiseled on W. face, alongside iron post and raise a mound of stone, 2 ft. base, 1½ ft. high W. of the corner.

Description of corner evidence found:

Found a 3" BLM brass cap, 0.2' out of the ground with mound of stones to the west, from which:

- A pine, 9" diam., bears S.73°42'E., 50', scribe visible.
- A fir, 10" diam., bears N.38°16'E., 17.5', healed scribe.
- A pine, 17" diam., bears N.88°06'W., 23.3', scribe visible.
- A pine, 12" diam., bears S.31°44'W., 63.9', scribe visible.
- A pine stump, 23" diam., bears S.14°36'W., 25.7', scribe visible.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Description of monument and accessories I established to perpetuate the original location of this corner:

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)

J-9

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-95