

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
July 1, 1882

80.00 Edge of timber, course S.60°E., set a post, 4 ft. long, 4 ins. square, 24 ins. in the ground for cor. to
secs. 10, 11, 14, and 15 marked

T10S S11 on N.E.

R37E S14 on S.E.

S15 on S.W. and

S10 on N.W. faces, with 4 notches on S. and 2 notches on E. edges from which:

A pine, 10 ins. diam., bears S.40°E., 29 lks. dist., mkd. T10S R 37E S14 BT.

A pine, 12 ins. diam., bears S.60°W., 29 lks. dist., mkd. T10S R 37E S15 BT.

A pine, 12 ins. diam., bears N.60°W., 19 lks. dist., mkd. T10S R 37E S10 BT.

No other trees within limits and dug a pit 18x18x12 ins. in sec. 11.

DIAGRAM
T 10 S

R 10 | 11
37 -----
E 15 | 14
1982

O.R.L.S 1898

Harry Christian Hildebrand RLS 1898
1982

At the corner location I found a 1" iron pipe set but no filling made. I also, when digging the hole for the brass cap, found pieces of the original wooden post.

The N60°W BT is a 38" stump 15.6 ft. marked E S10

The S40°E BT is a 26" stump 19.5 ft. marked S14

The SW BT is gone due to road construction.

I could not discern the pit that was set in Sec. 11.

I set a 2½" x 32" brass capped steel pipe in the original position 26" in the ground in a mound of stone, from which:

A ponderosa pine, 15" diam., bears S.43°E., 18.65', scribed "T10S R 37E S14 BT" with nail in NE base.

The corner is 13 ft. South of 4-strand barb wire fence.
No other bearing trees or objects available.

Bearings taken with a staff compass.

Declination set 18½"E. per 1980 Isogonic chart.

Distances pulled to 60d nails with brass washer marked L.S. 1898 set in side center of bearing trees.

Leland Lee Myres, RLS 699
1995

Found 1982 PLS 1898 brass cap in good condition, stamped as shown in diagram, with steel post set 4 ft. NE, from which:

A 17" ponderosa pine in good condition bears S44°30'E, 18.65 ft., with scribing visible.

A 46" ponderosa pine stump 36" high bears N62°W, 15.4 ft., with scribing visible.

Maintained corner by attaching "Land Surveying Monument" sign to steel post and bearing trees as needed, painted 6" wide red bands around bearing trees, and making new accessories:

A 17" ponderosa pine, bears N60°50'W, 135.8 ft., scribed T10SR37ES10BT.

A 13" ponderosa pine, bears S61°40'W, 95.4 ft., scribed T10SR37ES15BT.

A 20" ponderosa pine, bears N82°40'W, 46.0 ft., scribed T10SR37ES11BT.

Description of corner evidence found:

Found a 2" pipe with a brass cap in a small mound stone 0.3' above the ground, from which:

A pine, 16" diam., bears S.44°20'E., 18.6', scribed "T10SR37ES14BT", with nail and washer 1898.

A pine, 12" diam., bears S.61°40'W., 95.4', scribed "T10SR37ES15BT", with a washer in blaze "699 PLS" and a 60d on side.

A pine, 16" diam., bears N.60°47'W., 135.8', scribed "T10SR37ES10", with nail on side.

A stump, 39" diam., bears N.58°06'W., 16.3', scribed "S10".

A pine, 19" diam., bears N.36°44'E., 46.6', scribe visible and pitch covered.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Description of monument and accessories I established to perpetuate the original location of this corner:

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
by _____

(COUNTY OFFICIAL)

(DEPUTY)

J-17

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-97