

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
July 1, 1882

40.00 Set a post 3 ft. long, 3 ins. square, with marked stone 12 ins. in the ground for $\frac{1}{4}$ sec cor, marked $\frac{1}{4}$ S on west face, dug pits 18 x 18 x 12 ins, N. and S. of post $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft high, $3\frac{1}{2}$ ft. base around post.

DIAGRAM
T 10 S R 37 E
 $\frac{1}{4}$
S 15 | S 14
|
1995
RLS 1060

Description of corner evidence found:

Did not find any evidence of this corner.

Description of monument and accessories I established to perpetuate the original location of this corner:

No evidence of original monument found at a proportionate position, set a USFS $3\frac{1}{4}$ " aluminum capped monument 20" in the ground, with a mound of stone to cap, from which:

A $5/8$ " x 18" rebar, bears N. $84^{\circ}17'W.$, 12.6 ft., with brass washer "RLS 1060".

A $5/8$ " x 18" rebar, bears N. $41^{\circ}45'E.$, 32 ft., with brass washer "RLS 1060".

A $5/8$ " x 18" rebar, bears S. $3^{\circ}14'E.$, 37.2 ft., with brass washer "RLS 1060".

A cotton picker spindel set in a N-E fence line corner post, bears N. $9^{\circ}21'W.$, 1.7'.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 7-15-96

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

L-17

FILED 7-15-96

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-107