

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Not previously set.

DIAGRAM  
C  
1 |  
S -- | S 15  
16 |  
C  
RLS 1060  
1995

Description of corner evidence found:

Corner is being set this survey.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the point, determined by the procedures in the MANUAL OF INSTRUCTION FOR THE SURVEY OF PUBLIC LANDS, set a USFS 3 1/4" aluminum capped monument 12" in the ground, with 2 large stones mound to cap, from which:

A pine, 8" in diam., bears S.60°40'W., 34.8 ft., double blazed and scribed "CS1/16S15BT" with nail and brass washer "RLS 1060", on face of blaze.  
A pine, 6" in diam., bears N.30°50'W., 33.3 ft., double blazed and scribed "CS1/16S15BT" with nail and brass washer "RLS 1060", on face of blaze.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*R. David Schurian* 7-15-96

OREGON  
JUNE 18, 1976  
R. DAVID SCHURIAN  
1060

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_ I hereby certify that the within instrument was filed in this office  
for record on the \_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
\_\_\_\_\_ by \_\_\_\_\_

(COUNTY OFFICIAL)

(DEPUTY)

M-15

FILED 7-15-96  
BAKER COUNTY SURVEYOR  
SURVEY NO. 10-37-110