

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Graddon, U.S. Deputy Surveyor
July 1, 1882

39.75 Set a basalt stone 10 x 8 x 8 ins., 7 ins in the ground for the $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on N. face, from which:

- A pine, 15 ins. diam., bears N.50°W., 9 lks. dist., mkd. $\frac{1}{4}$ SBT.
- A pine, 30 ins. diam., bears S.55°E., 11 lks. dist., mkd. $\frac{1}{4}$ SBT.

DIAGRAM
T 10 S R 37 E

S 15
 $\frac{1}{4}$ -----
S 22

Owen C. Chatters, II and Lester E., Fisher, Cadastral Surveyors
July 26, 1974

The $\frac{1}{4}$ sec. cor. of secs. 15 and 22, monumented with the original basalt stone, 10 x 8 x 8 ins., firmly set 7 ins in the ground, mkd. $\frac{1}{4}$ on N. face, from which remains of the original bearing trees:

- A pine, 34 ins. diam., bears S.60°E., 9 lks. dist., mkd. $\frac{1}{4}$ SBT visible on open blaze.
(record, S.55°E., 11 lks.)
- A pine, 18 ins. diam., bears N.55°W., 10 $\frac{1}{2}$ lks. dist., mkd. $\frac{1}{4}$ SBT visible on open blaze.
(record, N.50°W., 9 lks.)

At the corner point

Set an iron post, 28 ins. long, 2 $\frac{1}{2}$ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

- A ponderosa pine, 9 ins. diam., bears N.51°E., 48 lks. dist., mkd. $\frac{1}{4}$ S15BT
- A fir, 8 ins. diam., bears S.29°W., 34 lks. dist., mkd. $\frac{1}{4}$ S22BT.

Bury corner stone alongside iron post.

Description of corner evidence found:

Found a 3" BLM brass cap, 0.2' above the ground no stones, from which:

- A pine, 21" diam., bears N.55°57'W., 6.9', with healed blaze.
- A fir, 12" in diam., bears S.41°40'W., 22.2 ft., with healed blaze.
- A pine, 12" in diam., bears N.50°42'E., 31.9 ft., With healed blaze.
- A pine, 9" in diam., bears S.33°17'E., 14.9 ft., double blazed and scribed " $\frac{1}{4}$ S22BT" with a brass washer "RLS 1060" nailed to the face of the blaze between the B and T.

Description of monument and accessories I established to perpetuate the original location of this corner:

Placed signs (54-2, 54-9) on trees and painted scars, blazes and a 6" red band around BT's.
Placed two steel fence posts three to five feet from corner near property line, with Forest Service signs (54-2).

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
_____ by _____

(COUNTY OFFICIAL)

(DEPUTY)

N-15

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

FILED 7-15-96

BAKER COUNTY SURVEYOR

RYEY NO: 10-37-114