



This section corner has been destroyed by dredging. Arthur H. Woodwell, R.P.E. Ore., No. 1738, found and identified the two stakes shown, in May, 1971. He says this was a part of his control for a North-South base line, established about 1940, for the relocation of the section corner. His East-West base line has been destroyed. I have extended his N-S base line to intersect a distance of 2,649.1 feet from the quarter corner shown. This distance was determined by using the proportion of the recently measured distance to the field note distance for the line between the East quarter corner and the Northeast corner of Section 4, T.10S., R.37E., W.M., and applying that factor to the field note distance from the quarter corner to the Southeast corner of Section 4.

REESTABLISHMENT OF CORNER TO SECTIONS 3, 4, 9 & 10, T.10S., R.37E., W.M.

SURVEY FOR JOHN A. LIENKAEMPER
LLOYD DINGER & JAMES HAMBLETON

SEPT., 1971

FILED 3-13-72
BAKER COUNTY SURVEYOR
SURVEY NO. 10-37-2

