

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original survey completed by William R. Graden under contract No. 409 dated March 1882
Set a post 4 ft long 4 ins square 24 ins in the ground for cor to Sec's 10, 11, 14, & 15
marked T10S S11 on NE; R37E S14 on SE; S15 on SW; and S10 on NW faces with 4 notches on S. and 2 notches on E. edges from which
A pine 10 ins diam bears S40°E 29 lks dist marked T10S R37E S14 BT
A pine 12 ins diam bears S60°W 29 lks dist marked T10S R37E S15 BT
A pine 12 ins diam bears N60°W 19 lks dist marked T10S R37E S10 BT
No other tree within limits and dug a pit 18X18X12 ins in Sec 11

| DIAGRAM | |
|---------|------|
| T10S | R37E |
| 10 | 11 |
| 15 | 14 |

Description of corner evidence found:

At the corner location I found a 1" iron pipe set but no filing made. I also, when digging the hole for the brass cap, found pieces of the original wooden post.
The N60°W BT is a 38" stump 15.6 ft. marked E S10
The S40°E BT is a 26" stump 19.5 ft. marked S14
The SW BT is gone due to road construction.
I could not discern the pit that was set in Sec 11.

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 2½" X32" brass capped steel pipe in the original position 26" in the ground in a mound of stone from which
A 15" Ponderosa Pine bears S43°E 18.65 ft. marked T10S R37E S14 BT Nail in NE base
The corner is 13 ft. South of 4-strand barb wire fence.
No other bearing trees or objects available.

Bearings taken with a staff compass.
Declination set 18½°E. per 1980 Isogonic chart.
Distances pulled to 60d nails with a brass washer marked L.S. 1898 set in side center of bearing trees.

Monument stamped:

| | | |
|----|---------------|----|
| | T10S | |
| R | 10 | 11 |
| 37 | | |
| E | 15 | 14 |
| | 1982 | |
| | O.R.L.S. 1898 | |



Office of.....Surveyor.....County of.....Baker.....
State of....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED July 19 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 10-37-10

☆ GPO—798-276