

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Hanley Engineering as a part of Three Bar Ranch Lands subdivision on July 14, 1972.

Set a 5/8-inch rebar with a yellow plastic cap marked RPE  
2808

**DIAGRAM**

T 10 S R 37 E  
C  
S  $\frac{1}{16}$  | S 4  
C

Description of corner evidence found:

Found a 5/8-inch rebar with extensively obliterated yellow plastic cap at a position which bears East, 1.11 feet from true corner position.

Description of monument and accessories established to perpetuate the original location of this corner:

At the true corner position set a 2½-inch brass cap on a 2-inch iron pipe 31 inches long and projecting 6 inches out of the ground with a surrounding rock mound.

Brass cap marked thus: T 10 S R 37 E

C  
S  $\frac{1}{16}$  | S 4  
C

1982

ORLS 1639

New bearing trees established:

A ponderosa pine, 14 inches diam bears S 78° W, 19.9 feet dist marked SC 1/16 S 4 BT  
A ponderosa pine, 7 inches diam bears S 47° W, 20.2 feet dist marked SC 1/16 S 4 BT

Each new bearing tree has a sign 54-3 attached below a 6 inch band of red paint and has a brass washer marked PLS 1639 nailed flush with lower BT blaze.

I hereby certify that the above corner monument was properly remonumented on August 3, 1982, by me and witnessed by Jim DeMastus.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 4, 1982

BAKER COUNTY SURVEYOR

SURVEY NO. 10-37-20

☆ GPO—790-276