

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Hanley Engineering as a part of Three Bar Ranch Lands subdivision on July 14, 1972.

Set a 5/8-inch rebar with a yellow plastic cap marked RPE
2808

DIAGRAM

T 10 S R 37 E

E $\frac{1}{16}$ S $\frac{4}{9}$

Description of corner evidence found:

Found a 5/8-inch rebar with a extensively obliterated yellow plastic cap at original corner position.

Description of monument and accessories | established to perpetuate the original location of this corner:

At the above noted position, replaced 5/8-inch rebar with a 2½-inch brass cap on a 2-inch iron pipe 31 inches long and projecting 6 inches out of the ground with a surrounding rock mound.

Brass cap marked thus: T 10 S R 37 E

E $\frac{1}{16}$ S $\frac{4}{9}$

1982

ORLS 1639

New bearing trees established:

A lodgepole pine, 11 inches diameter bears S 66° E, 7.7 feet dist marked E $\frac{1}{16}$ S 9 BT
A lodgepole pine, 9 inches diameter bears N 34° E, 2.8 feet dist marked E $\frac{1}{16}$ S 4 BT

Each new bearing tree has a sign 54-3 attached below a 6 inch band of red paint and has a brass washer marked PLS 1639 nailed flush with lower BT blaze.

I hereby certify that the above corner monument was properly remonumented on August 3, 1982, by me and witnessed by Jim DeMastus.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L Hanley

OREGON
JULY 14, 1973
WILLIAM L. HANLEY
1639

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 4, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 10-37-22

☆ GPO—790-276