

In 1971 the Bureau of Land Managment re-monumented the corners as follows:

The  $\frac{1}{4}$  corner of sections 5 and 8 monumented with a mound of stone, 2 ft. base, 1 ft. high, from which the remains of the original bearing trees:

A Pine stump 30" dia. bears  $N35^{\circ}W$ , 27 lks dist., no marks visible.

A Pine 18" dia. bears  $S50^{\circ}W$ , 54 lks dist., with scribe marks  $\frac{1}{4}$  S BT. visible on open blaze,

At Corner Point.

Set an iron post, 28" long  $2\frac{1}{2}$ " dia. 24" in the ground, with brass cap marked.

T10S R37E

$\frac{1}{4}$   $\frac{S5}{S8}$   
1971

From which new bearing trees.

A Fir 11" dia. bears  $N5^{\circ}E$ , 53 lks dist. marked  $\frac{1}{4}$  S5 BT.

A Ponderosa Pine 10" dia. bears  $S54\frac{1}{2}^{\circ}W$ , 69 lks dist., marked  $\frac{1}{4}$  S8 BT.

Bury basalt stone, 12"x8"x4" with an X chissled on N face, alongside iron post, and raise a mound of stone, 2 ft. base  $1\frac{1}{2}$ ft. high, N of the corner.