

In 1971 the Bureau of Land Managment re-monumented the corner as follows:

The corner of section 5,6,7, and 8, monumented with the original quartite stone (record basalt) 11x9x5" firmly set 6" in in the ground, no marks visible, from which the remains of the original bearing trees:

A Fir 25" dia. bears N35⁰E, 36 lks dist. with healed blaze.

A Western Larch 20" dia. bears S45⁰E, 12 lks dist. with healed blaze.

A Pine snag 42" dia. bears S55⁰W, 80 lks dist. with scribe marks T10S R37E S7 BT. visible on open blaze.

A Fir 30" dia. bears N33⁰W 36 lks dist. with healed blaze.

At the corner point.

Set an iron post 28" long 2½" dia. 24" in the ground, with brass cap marked.

T10S R37E

S6	S5
S7	S8

1971

From which new bearing trees.

A Western Larch 13" dia. bears S54⁰W, 39½ lks dist. mkd. T10S R37E S7 BT.

A White Fir 6" dia. bears S65⁰W, 54 lks dist. mkd. T10S R37E S7 BT.

No other trees available within limits.

Bury corner stone, to which I add an X ehissled on W. face alongside iron post.