

RECORD OF LAND CORNER MONUMENTATION

EAST 1/4 CORNER SECTION 15, T. 10 S., R. 38 E., W.M.

ORIGINALLY ESTABLISHED BY: William R. Gradon, U.S. Deputy Surveyor

GROUP NUMBER: 409

APPROVAL DATE: March 28, 1882

SUBSEQUENT SURVEYS:

- Reestablished by James Hanley, PE #2808 (and Baker County Surveyor). Survey filed March 28, 1966, as Survey No. 10-38-1, and associated Corner Monumentation Record filed as Survey No. 10-38-2 in the Baker County Surveyor's office.
- Corner maintenance activities performed November 15, 1990 by Douglas Ferguson, PLS #848, as evidenced by the Certified Record of Land Corner Monumentation filed January 22, 1992, as Baker County Survey No. 10-38-106.

9	10	10	11
16	15		15
16	15		15
21	22	22	23

ORIGINAL DESCRIPTION: Set a basalt stone 20x18x12 ins. 15 ins. in ground for 1/4 sec. cor. marked 1/4 on w face from which
a pine 24 ins dia bears S8°E 22 lks dist marked 1/4 S BT
a pine 18 ins dia bears S20°W 24 lks dist marked 1/4 S BT

SURVEY NO. 10-38-1 DESCRIPTION: Found, B.T. stump for Sec. 14. Set iron post monument with aluminum cap marked as shown.

SURVEY NO. 10-38-2 DESCRIPTION: Found B.T. stump for Sec. 14. Set 1-inch galvanized pipe with 2-inch aluminum cap marked as shown.

SURVEY NO. 10-38-106 DESCRIPTION: Found aluminum cap on steel pipe monument, stamped as shown on the DIAGRAM, as set by James Hanley at record measure from the Section 14 bearing tree, as shown on Baker County Survey No. 10-38-1. No work is needed on monument. From which:
Ponderosa Pine 18" dia., bears N45°15'W., 32.7 ft., Scribed: 1/4 S15 BT
Ponderosa Pine 14" dia., bears N74°15'E., 8.0 ft., Scribed: 1/4 S14 BT
Ponderosa Pine 14" dia., bears N10°02'W., 48.3 ft., Scribed: 1/4 S15 BT
Ponderosa Pine 16" dia., bears N33°36'E., 25.2 ft., Scribed: 1/4 S14 BT

EVIDENCE FOUND: Found 1" galvanized iron pipe with 2 1/2" aluminum cap, marked as shown below, projecting 6" above ground, in a 2 ft. diameter mound of stone.

From which, I FOUND A BEARING TREE BY FERGUSON:

- A ponderosa pine, 19" dbh, bears N.49°W., 32.63 ft., with healed blaze

Also from which, I SCRIBE A NEW BEARING TREE:

- A ponderosa pine, 18" dbh, bears N.52°E., 4.93 ft., marked 1/4 S14 in upper blaze and BT in lower blaze

Also from which, I SET NEW REFERENCE POINTS:

- A 5/8"x 12" iron pin, driven to failure, bears S.45°07'E., 15.81 ft., with attached 2" aluminum cap marked RP 1 2025 PLS 69454
- A 5/8"x 24" iron pin, driven to failure, bears S.45°16'W., 14.98 ft., with attached 2" aluminum cap marked RP 2 2025 PLS 69454

Painted a 6 inch red band around the bearing trees, and also painted the blazes red. Attached USFS 54-3 and 54-9 signs to BT's. Used RTK GPS to measure accessories. Distances to both bearing trees measured to a Mag Spike driven in the side-center-right above the root crown of each tree, with an attached 1 1/2" aluminum washer stamped PLS 69454. Set a steel fence post West, 5.1 ft., with USFS 54-2 sign attached, and another steel fence post North, 2.2 ft., with USFS 54-2 and 54-9 signs attached.

RESTORATION BY, STAMP AND DATE:


Work Performed May 1, 2025

Jason L. Hatfield, PLS
Spencer B. Jones, Survey Tech

USDA FOREST SERVICE
NORTHEAST OREGON LAND ZONE
1550 Dewey Avenue, Suite A
Baker City, OR 97814
(541) 523-1283

FILED June 3, 2025
BAKER COUNTY SURVEYOR
SURVEY NO. 10-38-177

CORNER MONUMENT
MARKED:



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Jason L. Hatfield

OREGON
NOVEMBER 30, 2007
JASON L. HATFIELD
#69454

EXPIRES: 6/30/2027