

RECORD OF SURVEY IN PORTIONS OF SECTIONS 16, 17, 18, 19, 20 & 21 OF TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON, FOR JOHN & KAREN PATTERSON DURING THE MONTHS OF JUNE TO DECEMBER 2001.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Richard A. Shaver
OREGON
JULY 22, 1974
RICHARD A. SHAVER
1015

TIMBERLINE SURVEYS
P.O. BOX 61
WALLOWA, OREGON 97885
PHONE 541-886-2605
REGISTRATION EXPIRES
6/30/02

NOTES:

- (1) NORTHWEST CORNER SECTION 18, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND STONE, 20" X 10" X 10" WITH 4 NOTCHES ON THE SOUTH FACE AND 2 NOTCHES ON THE NORTH FACE IN SMALL MOUND OF STONE UNDER A SAGEBRUS 2 FEET WEST OF A CATTLE TRAIL. I REPLACED THE STONE WITH A 5/8" DIAMETER X 30" LONG IRON ROD WITH AN ALUMINUM CAP MARKED: "T10S R43E 12 | 7 T10S R44E 13 | 18 LS1015 2001"
- SET ORIGINAL STONE ALONGSIDE THE NEW MONUMENT.
FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 31° WEST 12.87 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 47° EAST 13.57 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 58° EAST 10.27 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 45° WEST 15.30 FEET.
- (2) NORTH 1/4 CORNER SECTION 18, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND STONE 11" X 9" X 9" WITH PARTIAL 4 ON NORTH FACE. I REPLACED THE STONE WITH A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 2" DIAMETER ALUMINUM CAP MARKED "T10S R44E 1/4 7 | 18 LS1015 2001"
- FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 19° WEST 4.57 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 50° EAST 4.75 FEET.
- (3) WEST 1/4 CORNER SECTION 18, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND STONE 8" X 10" X 24" WITH 1/4 ON WEST FACE, REPLACED WITH A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 2" DIAMETER ALUMINUM CAP MARKED: "LS1015 T10S R43E 1/4 13 | 18 T10S R44E 2001"
- SET ORIGINAL STONE ALONGSIDE THE NEW MONUMENT.
FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 18° EAST 6.48 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 14° EAST 9.47 FEET.
FOUND AN OLD EAST-WEST FENCE DOWN AND PARTIALLY COVERED BY DIRT 24 FEET NORTH OF CORNER POINT.
- (4) EAST 1/4 CORNER SECTION 18, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND STONE 14" X 9" X 7" WITH PORTION OF FAINT 1/4 ON WEST FACE. REPLACED STONE WITH A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 2" DIAMETER ALUMINUM CAP MARKED "T10S R44E 18 | 17 LS1015 2001"
- SET STONE ALONGSIDE THE NEW MONUMENT.
FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 71° EAST 17.07 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP BEARS SOUTH 56° WEST 17.56 FEET.
A 3.75" DIAMETER U.S.G.S. BRONZE DISC SET IN ROCK MARKED: U.S. GEOLOGICAL SURVEY B.M. MERIDIAN MARK BEARS SOUTH 28°06'29" WEST 830.89 FEET.

- (5) SOUTHWEST CORNER SECTION 18, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND STONE 22" X 20" X 8" WITH 3 NOTCHES ON SOUTH FACE. REPLACED STONE WITH A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 2" DIAMETER ALUMINUM CAP MARKED: "2001 T10S R43E 13 | 18 T10S R44E 24 | 19 LS1015"
- SET STONE ALONGSIDE NEW MONUMENT.
FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP BEARS NORTH 43° WEST 18.08 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 2° EAST 23.03 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 46° EAST 28.32 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 84° WEST 18.15 FEET.
AN OLD DOWN NORTH-SOUTH FENCE GOES RIGHT OVER THE CORNER POSITION.
- (6) SOUTH 1/4 CORNER SECTION 18, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND STONE 11" X 9" X 4" WITH 1/4 ON SOUTH FACE IN SMALL MOUND OF STONE. I REPLACED THE STONE WITH A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 2" DIAMETER ALUMINUM CAP MARKED: "T10S R44E 1/4 18 | 19 LS1015 2001"
- THE STONE WAS SET ALONGSIDE THE NEW MONUMENT.
FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 23° EAST 24.18 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 56° WEST 18.22 FEET.
THE REMAINS OF ORIGINAL 36" DIAMETER FIR BEARS NORTH 29° WEST 77.00 FEET.
- (7) PROPORTIONED SOUTHEAST CORNER OF SECTION 18, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: NO MONUMENT FOUND. AT DOUBLE PROPORTIONATE DISTANCE I SET A 5/8" X 30" LONG IRON ROD WITH A 2" DIAMETER ALUMINUM CAP MARKED: "T10S R44E 18 | 17 19 | 20 LS1015 2001"
- FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 30° WEST 7.13 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 42° EAST 16.19 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 40° EAST 6.86 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 70° WEST 9.54 FEET.
CORNER POSITION IS IN AN AREA OF LARGE BOULDERS.
- (8) SOUTHEAST CORNER SECTION 17, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND 3.25" DIAMETER BRASS DISC ON A 2.5" DIAMETER IRON PIPE MARKED: "T10S R44E S17-S16 S20-S21 1965"
- SEE BUREAU OF LAND MANAGEMENT SURVEY DATED 1965 UNDER SPECIAL INSTRUCTIONS DATED JUNE 21, 1965, FOR GROUP 262, OREGON.

- (9) 1/4 CORNER SECTIONS 16/21, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND 3.25" DIAMETER BRASS CAP ON A 2.5" DIAMETER IRON PIPE MARKED: "S16 S21 T10S R44E 1965"
- SEE BUREAU OF LAND MANAGEMENT SURVEY DATED 1965, UNDER SPECIAL INSTRUCTIONS DATED JUNE 21, 1965, FOR GROUP 262, OREGON.
- (10) SOUTHEAST CORNER SECTION 16, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND 3.25" DIAMETER BRASS CAP ON A 2.5" DIAMETER IRON PIPE MARKED: "T10S R44E S 16-S 15 S 21-S 22 1965"
- SEE BUREAU OF LAND MANAGEMENT SURVEY DATED 1965, UNDER SPECIAL INSTRUCTIONS DATED JUNE 21, 1965, FOR GROUP 262, OREGON.
- (11) 1/4 CORNER SECTION 19, 20, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND STONE 14" X 12" X 9" WITH 1/4 ON THE WEST FACE IN SMALL MOUND OF STONE. I REPLACED THE STONE WITH A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 2" DIAMETER ALUMINUM CAP MARKED: "T10S R44E 1/4 19 | 20 LS1015 2001"
- SET ORIGINAL STONE ALONGSIDE NEW MONUMENT.
FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 50° WEST 36.11 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 40° EAST 31.32 FEET.
ORIGINAL 36" PINE ROOT CIRCLE SOUTH 41° EAST 55.44 FEET
- (12) 1/4 CORNER SECTIONS 21 & 22, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: FOUND 3.25" DIAMETER BRASS CAP ON A 2.5" DIAMETER IRON PIPE MARKED: "T10S R44E 1/4 S 21 | S 22 1979"
- SEE BUREAU OF LAND MANAGEMENT SURVEY DATED 1979 UNDER SPECIAL INSTRUCTIONS DATED AUGUST 7, 1979, UNDER GROUP NUMBER 992, OREGON.
- (13) FOUND A 3.75" DIAMETER U.S.G.S. BRONZE DISC SET IN ROCK, MARKED: "U.S. GEOLOGICAL SURVEY B.M. MERIDIAN MARK"
- A, B, D, E, F, G, H & J: 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" SET NOVEMBER 15 TO DECEMBER 1, 2001.
- (14) CENTER 1/4 CORNER SECTION 18, TOWNSHIP 10 SOUTH, RANGE 44 EAST OF THE WILLAMETTE MERIDIAN IN BAKER COUNTY, OREGON: SET A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 2" DIAMETER ALUMINUM CAP MARKED: "T10S R44E C1/4 S18+ LS1015 2001"
- FROM THE CORNER POINT:
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 56° WEST 13.73 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS NORTH 30° EAST 7.34 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 67° EAST 9.02 FEET.
A 5/8" DIAMETER X 30" LONG IRON ROD WITH A 1.3" DIAMETER YELLOW PLASTIC CAP MARKED "LS1015" BEARS SOUTH 01° 10.38 FEET.
AN OLD EAST-WEST DOWN FENCE IS 3 FEET SOUTH OF CORNER POINT.