CERTIFIED RECORD OF LAND CORNER MONUMENTATION


Northwest corner section 18, T. 10 S., R. 44 E., of the W.M.

History of original corner

Original corner set by N. Walden Deputy Surveyor under contract No. 198, dated July 15, 1873 Set basalt stone 22"x10"x10".

Subsequent survey:

W.B. Barr survey under contract no. 388 Dated May 7, 1881 found stone 22" x 10" x 10".



Description of evidence found:

Found stone 22" x 10" x 10" with 4 notches on the south face and 2 notches on the north face in small mound of stone under a sagebrush 2 feet west of a cattle trail.

Description of monument and accessories

established to perpetuate the location of this corner:

Set a 5/8" diameter x 30" long iron rod and 2" Diameter aluminum cap marked:

From the corner point:

A 5/8" diameter x 30" long iron rod with a 1.3" diameter yellow plastic cap marked "LS1015" bears North 31° West 12.87 feet.

A 5/8" diameter x 30" long iron rod with a 1.3" diameter yellow plastic cap marked "LS1015" bears North 47° East 13.57 feet.

A 5/8" diameter x 30" long iron rod with a 1.3" diameter yellow plastic cap marked "LS1015" bears South 58° East 10.27 feet.

A 5/8" diameter x 30" long iron rod with a 1.3" diameter yellow plastic cap marked "LS1015" bears South 45° West 15.50 feet.

Deposited stone alongside new monument. Compass declination 19° East.

I hereby certify that the above corner point was perpetuated as herein described on 11/15/01.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 22, 1974
RICHARD A. SHAVER

BAKER COUNTY SURVEYOR
SURVEY NO. 10 - 44 - 3

CP#83

Timberline Surveys P.O. Box 61 Wallowa, Oregon 97885 Phone 541-886-2605 Registration expires 6/30/02

Office of County Surveyor for t	he County of Baker, State o	of Oregon, I hereby	
Certify that the within instrumen	nt was filed in this office fo	r record on the	
day of	2002	. *	,
		<u> </u>	
	by		
(county official)	·	(deputy)	