

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

TOWNSHIP 10 SOUTH, RANGE 44 EAST

Southeast corner section 18,
T. 10 S., R. 44 E. of the W.M.

History of original corner

Original corner set by W.B. Barr
Deputy Surveyor under contract
Number 388, dated May 7, 1881.
Set marked basalt rock 14" x 12"
x 9" raised Mound of stone per instructions.

Subsequent survey:

None.

Description of evidence found:

None.

Description of monument and accessories

established to perpetuate the location of this corner:

At double proportionate distance I set a 5/8" diameter x 30" long iron rod and 2" Diameter aluminum cap marked:

T10S R44E
18 | 17
19 | 20
LS1015
2001 in mound of stone.

From the corner point:

A 5/8" diameter x 30" long iron rod with a 1.3" diameter yellow plastic cap marked "LS1015" bears North 30° West 7.13 feet.

A 5/8" diameter x 30" long iron rod with a 1.3" diameter yellow plastic cap marked "LS1015" bears North 42° East 16.19 feet.


A 5/8" diameter x 30" long iron rod with a 1.3" diameter yellow plastic cap marked "LS1015" bears South 40° East 6.86 feet.

A 5/8" diameter x 30" long iron rod with a 1.3" diameter yellow plastic cap marked "LS1015" bears South 70° West 9.54 feet.


Compass declination 19° East.

Corner position falls in a clump of large boulders.

I hereby certify that the above corner point was perpetuated as herein described on 11/16/01.



Richard A. Shaver



Timberline Surveys
P.O. Box 61
Wallowa, Oregon 97885
Phone 541-886-2605
Registration expires
6/30/02

FILED JUNE 3, 2002
BAKER COUNTY SURVEYOR
SURVEY NO. 10-44-9
CP# 89

Office of County Surveyor for the County of Baker, State of Oregon, I hereby
Certify that the within instrument was filed in this office for record on the
..... day of 2002

.....by.....
(county official) (deputy)

