


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. B-15

History of original corner establishment:

Baker County Survey Records show no previous establishment of this Cor.



Description of corner evidence found:

Baker County Survey Records show no previous establishment of this Cor.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 28" in the ground.

From Which:

Set 5/8"x30" iron pins with plastic caps marked PLS 848 and steel guard post with Warning, Boundary and Bearing Tree signs wired to each post as follows S 0°14'W., on property line, 13.2 ft. and S89°08'E on property line, 55.8 ft. from the corner.

Measurements to pins taken with Electronic Tacheometer with bearings turned from the survey control network.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

**OREGON
JULY 12, 1938
DOUGLAS M. FERGUSON
848**

This work is performed by:
Douglas M. Ferguson PLS 848
Mt. Vernon Oregon.
On: Aug. 8, 1988
Refer to Map of Survey No. 11-36-17
Witnesses: D. Mitchell Ferguson & Ken Delano

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 3-30-89
BAKER COUNTY SURVEYOR
SURVEY NO. 11-36-23