


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. E-15

History of original corner establishment:

Corner was originally established by Wm.R. Gradon, in March 1882, under General Land Office Contract No. 409. The U.S. Surveyor Generals Notes State: Set a sandstone 10x10x7 ins. 7 ins. in the ground for 1/4 sec. cor. marked 1/4 on N face.



from which:

A Pine 16 ins. diam bears N15°W., 97 lks. dist. marked 1/4 S BT  
A Pine 10 ins. diam bears S 7°W., 18 lks. dist. marked 1/4 S BT

Description of corner evidence found:

Found 12"x10"x7" stone set vert. in the ground with 1/4 X marked on the N face.

Bearing Trees have been lost to logging.  
Accepted the above described stone as the 1/4 Corner.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the **DIAGRAM**, SET 28" in the ground.

From Which:

Ponderosa Pine 14" dia., Bears N72°59'E., 37.7 ft., scribed: 1/4 S3 BT  
Lodgepole Pine 10" dia., Bears S15°57'E., 25.0 ft., scribed: 1/4 S10 BT  
Measurements to trees taken with Electronic Tacheometer with bearings turned from the survey control network.  
Nailed a brass washer stamped PLS 848 on blaze above BT scribe, Bearing Tree Sign above blaze, and warning sign on back of each tree. Painted a 6" red band at breast ht. around each tree. Set steel fence post with warning Sign, North 4 ft. from the corner.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

**OREGON  
JULY 12, 1888  
DOUGLAS M. FERGUSON  
848**

This work is performed by:  
Douglas M. Ferguson PLS 848  
Mt. Vernon Oregon.  
On: Aug. 17, 1988  
Refer to Map of Survey No. 11-36-17  
Witnesses: D. Mitchell Ferguson & Mallee Wood

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)