

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Douglas M. Ferguson, PLS 848, on August 8, 1988 under U.S. Forest Service contract.

Ferguson's record states:

Set 2-1/2"x30" aluminum pipe with 3-1/2" aluminum cap, stamped as shown on the DIAGRAM, set 28" in the ground.


From which:

Set 5/8"x30" iron pins with plastic caps marked PLS 848 and steel guard posts with Warning, Boundary, and Bearing Tree signs wired to each post as follows: S0°14'W, on property line, 13.2 ft. and S89°08'E on property line, 55.8 ft. from the corner.

Measurements to pins taken with Electronic Tacheometer with bearings turned from the control network.

B-15

DIAGRAM



Description of corner evidence found:

Found 2 1/2" (record 3 1/2") diameter aluminum cap on aluminum pipe buried 6" under ground in North Fork Burnt River floodplain. From which:

A 5/8"x30" rebar with yellow plastic cap stamped PLS 848 bears S0°14'W, 13.2' with steel fence post behind it with 54-2, 54-3, and 54-9 signs.

No trace of accessory to SE, believe it was destroyed by North Fork Burnt River.

Description of monument and accessories I established to perpetuate the original location of this corner:

Dig out corner monument and place a 3' long railroad tie 1' west of monument.

New accessory:

A 2" aluminum cap on 5/8"x30" rebar, bears S60°W, 52.0', marked as shown below, flush with ground. Install an aluminum fencepost behind cap with 54-9 sign.

Install guard posts on south and east property lines 5' from corner monument with 54-2 and 54-9 signs.

Corner monument is approximately 35' west and 40' north of North Fork Burnt River.

Geodetic Coordinates (NAD83):

N 44°38'35.4"

W 118°16'56.6"

Geodetic coordinates were obtained from a Garmin recreational grade GPS receiver and have been averaged.

Date: July 1, 2014

Declination: 14 1/2° E

Witnesses: Lisa Adair

Dan Lee

Toribio Quinones



REGISTERED
PROFESSIONAL
LAND SURVEYOR

Kenneth A. Lind

OREGON
JULY 19, 1994
KENNETH A. LIND
2672

Renews: 12-31-14

FILED Oct. 23, 2014

BAKER COUNTY SURVEYOR

SURVEY NO. 11-36-34