

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Herman D. Gradon under GLO contract No. 416 dated August 19, 1881.

Surveyor's General record states:

Set a sandstone 18x12x6 ins., 12 ins. in the ground for 1/4 sec. cor. marked 1/4 on N face and raised a mound of stone alongside.

DIAGRAM

T 11 S R 37 E

$\frac{1}{4}$	$\frac{S\ 17}{S\ 20}$
---------------	-----------------------

Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2 inch brass cap on a 2 inch iron pipe, 31 inches long, 26 inches in the ground with a 6 foot steel fence post alongside with signs 54-4 and 54-2 attached from which:

New bearing tree

A juniper, 8 ins diam bears N 29° W, 273.0 ft dist mkd 1/4 S 17 BT with a sign 54-3 below a band of red paint and a brass washer mkd LS 1206 flush to BT blaz. There being no other trees available, I set a brass capped monument of identical construction to corner monument which bears S 88°10'47" E, 20.56 ft dist marked thus:

T 11 S R 37 E
R M
← $\frac{1}{4}$ S 17
4 S 20
20.56 ft

1978
ORLS 1206

Corner monument marked thus:

T 11 S R 37 E
 $\frac{1}{4}$ S 17
4 S 20
1978
ORLS 1206

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

I hereby certify the above corner monument was correctly re-established on June 15, 1978 witnesses by B. Hanley, R. Spivey, and C. Race.

Office of.....County Surveyor..... County of..... Baker

State of... Oregon..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO : 798-276

FILED 6-30-78

BAKER COUNTY SURVEYOR

SURVEY NO. 11-37-11