

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.

DIAGRAM

T 11 S R 37 E

NW $\frac{1}{16}+$ S 29

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 $\frac{1}{4}$ inch brass cap on a 2 inch iron pipe 31 inches long, 23 inches in the ground to bedrock with a dirt and rock mound and a 6 foot steel fence post alongside with a sign 54-9 attached from which:

New bearing trees:

A pine 5 ins diam bears S 39° W, 33.9 ft dist marked 1/16 S 29 BT
A pine 10 ins diam bears S 05° W, 59.6 ft dist marked 1/16 S 29 BT

Each BT has a sign 54-3 attached 6 inches below a band of red paint and has a brass washer marked LS 1206 nailed flush with BT blaze.

Brass cap marked thus: T 11 S R 37 E

NW $\frac{1}{16}+$ S ~~X~~₂₉

1978
. ORLS 1206

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

I hereby certify the above corner monument was correctly established on June 14, 1978 witnessed by T. Hanley, R. McKim, and T. Fisk.

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon.....I hereby certify that the within instrument was filed in this office
for record on the.....day of....., 19.....
.....by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO : 798-276

FILED 6-30-78

BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-14