

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Herman D. Gradon under GLO contract No. 416 dated August 19, 1881.

Surveyor's General records state:

Set a sandstone 18x12x10 ins, 12 ins in the ground for 1/4 sec cor marked 1/4 on N face and raised mound of stone alongside.

DIAGRAM

T 11 S R 37 E	
$\frac{1}{4}$	$\frac{S 18}{S 19}$

Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 $\frac{1}{2}$ inch brass cap on a 2 inch iron pipe 31 inches long, 26 inches in the ground with a 6 foot steel fence post alongside with a sign 54-4 attached, from which:

New bearing trees:

A juniper, 10 ins diam bears S 03° E, 11.0 ft dist marked 1/4 S 19 BT
A juniper, 17 ins diam bears N 10° W, 42.3 ft dist marked 1/4 S 18 BT

Each BT has a sign 54-3 attached 6 inches below a band of red paint and has a brass washer marked LS 1206 nailed flush with BT blaze.

Brass cap marked thus: T 11 S R 37 E

$\frac{1}{4}$	$\frac{S 18}{S 19}$
---------------	---------------------

1978
ORLS 1206

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

I hereby certify the above corner monument was re-established on June 9, 1978 witnessed by B. Hanley and C. Race.

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon.....I hereby certify that the within instrument was filed in this office
for record on the.....day of....., 19.....
.....by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 6-30-78

BAKER COUNTY SURVEYOR

SURVEY NO. 11-37-16