

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Herman D. Gradon under GLO contract No. 416 dated August 19, 1881.

Surveyor's General records state:

Set a basalt stone 16x8x5 ins., 11 ins. in the ground for 1/4 sec cor marked 1/4 on N face from which

A pine, 6 ins diam bears N 05° E, 95 lks dist marked 1/4 S BT
A pine, 24 ins diam bears S 30° W, 56 lks dist marked 1/4 S BT

DIAGRAM

T 11 S R 37 E	
$\frac{1}{4}$	$\frac{S 30}{S 31}$

Description of corner evidence found:

None

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2 inch brass cap on a 2 inch iron pipe, 31 inches long, 27 inches in the ground with a 6 foot steel fence post alongside with a sign 54-4 attached, from which

New bearing trees:

A pine, 8 ins diam bears S 31° W, 23.0 ft dist marked 1/4 S 31 BT
A fir, 6 ins diam bears N 85° W, 21.7 ft dist marked 1/4 S 30 BT

Each BT has a sign 54-3 attached 6 inches below a band of red paint and has a brass washer marked LS 1206 nailed flush with BT blaze.

Brass cap is marked thus: T 11 S R 37 E

$\frac{1}{4}$	$\frac{S 30}{S 31}$
---------------	---------------------

1978
ORLS 1206

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

I hereby certify the above corner monument was correctly re-established on June 15, 1978 witnessed by B. Hanley and C. Race.

Office of.....County Surveyor..... County of.....**Baker**.....
State of.....**Oregon**..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFIC(AI))

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 6-30-78

BAKER COUNTY SURVEYOR

SURVEY NO. 11-37-21