

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.

DIAGRAM

T 11 S R 37 E

NE 1/16 S 30

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½ inch brass cap on a 2 inch iron pipe, 31 inches long, 23 inches in the ground with a 6 foot steel fence post alongside with signs 54-2 and 54-9 attached from which:

New bearing trees:

A pine, 9 ins. diam. bears S. 43° E., 21.5 ft. dist. marked 1/16 S 30 BT
A pine, 9 ins. diam. bears S. 16° W., 39.9 ft. dist. marked 1/16 S 30 BT

Both BT have a sign 54-3 attached 6 inches below a band of red paint and has a brass washer marked LS 1206 nailed flush with BT blaze.

Brass cap marked thus:

T 11 S R 37 E

NE 1/16 S 30

1978

ORLS 1206

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 24, 1977
JAMES D. HANLEY
1206

I hereby certify the above corner monument was correctly established on June 15, 1978 witnessed by T. Hanley, R. McKim and T. Fisk.

Office of.....County Surveyor.....County of.....Baker
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the.....day of....., 19.....
.....by.....
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO-798-276

FILED 6-30-78

BAKER COUNTY SURVEYOR

SURVEY NO. 11-37-24