

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.

DIAGRAM

T 11 S	R 37 E
	S 18
E 1/16	<u>S 19</u>

Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner

Set a 2½ inch brass cap on a 2 inch iron pipe, 31 inches long, 26 inches in the ground with a 6 foot steel fence post alongside with signs 54-2 and 54-9 attached from which:

New bearing trees:

A pine, 6 ins. diam. bears N. 20° E., 29.0 ft. dist., marked 1/16 S 18 BT
A pine, 6 ins. diam. bears N. 64° E., 44.0 ft. dist., marked 1/16 S 18 BT

Each BT has a sign 54-3 attached 6 inches below a band of red paint and has a brass washer marked LS 1206 nailed flush with BT blaze.

Brass cap marked thus:

T 11 S R 37 E

	S 18
E 1/16	<u>S 19</u>

1978

ORLS 1206

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

I hereby certify the above corner monument was correctly established on June 19, 1978 witnessed by B. Hanley, R. Spivey and C. Race.

Office of _____ County Surveyor _____ County of _____ Baker
State of _____ Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____

(COUNTY OFFICIAL) by _____
(DEPUTY)

FILED 6-30-78
BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-28