


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



Description of corner evidence found:

Description of monument and accessories I established to perpetuate the original location of this corner

Set a 2 $\frac{1}{2}$ inch brass cap on a 2 inch iron pipe, 31 inches long, 26 inches in the ground and a 6 foot steel fence post alongside with a sign 54-9 attached, from which

New bearing trees:

A juniper, 6 ins diam bears S 43°30' W, 6.1 ft dist marked C 1/4 S 20 BT
A juniper, 10 ins diam bears S 46° E, 42.9 ft dist marked C 1/4 S 20 BT

Each BT has a sign 54-3 attached 6 inches below a band of red paint and has a brass washer marked LS 1206 nailed flush with BT blaze.

Brass cap is marked thus: T 11 S R 37 E

C $\frac{1}{4}$ S 20

1978
ORLS 1206

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley

OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

I hereby certify the above corner monument was correctly established on July 7, 1978 witnessed B. Hanley, and R. Spivey.

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the day of
by (COUNTY OFFICIAL) (DEPUTY)

FILED 7-31-78
BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-34