

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.

DIAGRAM	
T 11 S	R 37 E
C 1/4	S 30

Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2½ inch brass cap on a 2 inch iron pipe, 31 inches long, 26 inches in the ground with a 6 foot steel fence post alongside with a sign 54-9 attached from which:

New bearing trees:

A pine, 14 ins. diam. bears S. 27° W., 13.0 ft. dist. marked C 1/4 S 30 BT
A juniper, 10 ins. diam. bears S. 42° E., 41.6 ft. dist. marked C 1/4 S 30 BT



Each BT has a sign 54-3 attached 6 inches below a band of red paint and has a brass washer marked LS 1206 nailed flush with BT blaze.

Brass cap marked thus:

T 11 S R 37 E

C 1/4 S 30

1978
ORLS 1206



I hereby certify the above corner monument was correctly established on July 7, 1978, witnessed by B. Hanley, R. Spivey and R. McKim

Office of..... County Surveyor..... County of..... Baker
State of..... Oregon....., I hereby certify that the within Instrument was filed in this office
for record on the day of
..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 7-31-78
BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-35