

In 1974 the Bureau of Land Managment re-monumented this corner as follows.

The $\frac{1}{4}$ section corner of secs. 15 and 22, monumented with the original basalt stone, (record sandstone) 16x8x5 ins. loosly set in a mound of stone $2\frac{1}{2}$ ft. base 1 ft. high, marked $\frac{1}{4}$ on N face, from which the remains of the original bearing trees:

A Juniper 22" dia. bears S85⁰W, 28 lks dist., with ax marks visible on partially healed double blaze.

At the corner point.

Set an iron post 28" long $2\frac{1}{2}$ " dia. 6" in the ground, to solid rock, supported in a mound of stone, 6 ft. base, to top with brass cap marked.

T11S R37E

$\frac{1}{4}$ S15

S22

1974

From which a new bearing tree.

A Juniper 8" dia. bears N27⁰W, 84 lks dist., marked $\frac{1}{4}$ S15 BT.

Deposit corner stone alongside iron post.