

In 1974 the Bureau of Land Managment re-monumented this corner as follows.

The $\frac{1}{4}$ section corner of secs. 21, and 22, monumented with the original basalt stone, (record sandstone) 14x10x10 ins. firmly set 2" in the ground, and in a mound of stone, $3\frac{1}{2}$ " ft. base 1 ft. high, marked $\frac{1}{4}$ on W face from which the original bearing tree:

A Juniper 13" dia. bears $S5^{\circ}W$, 170 lks dist., with illegible scribe marks visible on partially healed double blaze (record $S10^{\circ}W$, 174 lks.)

At the corner point.

Set an iron post, 28" long $2\frac{1}{2}$ " dia., 14 " in the ground, to solid rock, and in a mound of stone, 4 ft. base, to top, with brass cap marked.

T11S R37E
 $\frac{1}{4}$
S21 | S22
1974

From which a new bearing tree.

A Juniper 8" dia. bears $S73^{\circ}E$, 102 lks dist., marked $\frac{1}{4}$ S22 BT.

Deposit corner stone alongside iron post.

Corner is located in old fence line, bears N and S.