

In 1974 the Bureau of Land Management re-monumented this corner as follows:

The $\frac{1}{4}$ sec. cor. of secs. 15 and 16 monumented with the original basalt stone, 16x7x7 ins. firmly set 7" in the ground, marked $\frac{1}{4}$ on W face, from which the remains of the original bearing trees.

A Mountain Mahogany 11" dia. bears N53⁰E, 114 lks dist., with scribe marks $\frac{1}{4}$ S BT. visible on partially healed double blaze. (record N50⁰E)

A Mountain Mahogany snag 8" dia. bears N45⁰W, 70 lks dist., with scribe marks $\frac{1}{4}$ S BT visible on open blaze.

At corner point.

Set an iron post 28" long 2 $\frac{1}{2}$ " dia. 24" in the ground, with brass cap marked.

T11S R37E

S16 $\frac{1}{4}$ S15

1974

From which new bearing trees.

A Juniper 7" dia. bears S42⁰E, 49 lks dist., marked $\frac{1}{4}$ S15 BT.

A Juniper 10" dia. bears S85⁰W, 21 $\frac{1}{2}$ lks dist., marked $\frac{1}{4}$ S16 BT.

Deposit corner stone alongside iron post.