

In 1974 the Bureau of Land Managment re-monumented this corner from original evidence as follows:

The corner of secs. 14, 15, 22, and 23, monumented with the original unmarked sandstone, 16x12 x8 ins., loosely set 2" in the ground, from which the remains of the original bearing trees;
A Fir snag 32" dia. bears N88°E, 79 lks dist., with healed double blaze. (record N85°E)
A Ponderosa Pine stump 20" dia. bears S40°E, 100 lks dist., no marks visible.
A " " " 36" dia. bears S15°W, 54 lks dist., no marks visible.
A Mountain Mahogany snag 6" dia. bears N35°W, 44 lks dist., with scribe marks R3 visible on open double blaze.

At corner point.

Set an iron post, 28" long 2½" dia., 24" in the ground, with brass cap mkd.

T11S R37E

S15 S14

S22 S23

1974

From which new bearing trees:

A Fir 6" dia. bears N10°E, 22 lks dist., marked T11S R37E S14 BT.
A Ponderosa Pine 13" dia. bears S47°E, 178 lks dist., marked T11S R37E S23 BT.
A " " 12" dia. bears S53°W, 181 lks dist., marked T11S R37E S22 BT.
A Fir 8" dia. bears N32°W, 49 lks dist., marked T11S R37E S15 BT.
Deposit corner stone alongside iron post.