

In 1974 the Bureau of Land Managment re-monumented this corner as follows:

The corner of sections 9,10,15, and 16, monumented with the original basalt stone,(record, sandstone) 14x10x8 ins., firmly set 10" in the ground, marked with 4 grooves on S face, and 3 grooves on E. face, from which the remains of the original bearing trees:

A Ponderosa Pine 15" dia. bears N30°E, 25 lks dist. with healed double blaze.

A White Fir snag 20" dia. bears S55°E, 47 lks dist. with healed double blaze.

A White Fir stump 24" dia. bears S10°W, 47 lks dist., no marks visible.

A Larch 23" dia. bears N35°W. 41 lks dist. with scribe marks S9 bt visible on partially healed double blaze.

At the corner point.

Set an iron post, 28 ins. long 2½ ins. dia., 16 ins in the ground, to solid rock, and in a mound of stone, 3½ ft. base, to top, with brass cap marked..

T11S R37E

|     |     |
|-----|-----|
| S9  | S10 |
| S16 | S15 |

1974

From which new bearing trees.

A Ponderosa Pine 11", 11" dia. bears S60°E, 32 lks dist., marked T11S R37E S15 BT.

A " " 14" dia. bears S41°W, 17½ lks dist. marked T11S R37E S16 BT.

Deposit corner stone alongside iron pipe.