

In 1974 the Bureau of Land Managment re-monumented this corner as follows.

The  $\frac{1}{2}$  section corner of secs. 16 and 21, monumented with the original basalt stone, (record sandstone) 14x10x5 ins., loosly set 3 ins. in the ground, marked  $\frac{1}{2}$  on N face, From which the remains of the original bearing trees:

A root hole, bears North, 154 lks dist., with a down Ponderosa Pine alongside, 24" dia., with fragmenary scribe marks visible on open blaze.

A root hole, bears S25°E, 107 lks dist., with a down Ponderosa Pine alongside, 36" dia. with healed blaze.

At the corner point.

Set an iron post, 28 ins. long, 2 $\frac{1}{2}$ " dia., 24" in the ground, with brass cap marked.

T11S R37E

S16

$\frac{1}{2}$ S21

1974

From which new bearing trees.

A Ponderosa Pine 8" dia. bears N63°W, 41 $\frac{1}{2}$  lks dist., mkd.  $\frac{1}{2}$  S16 BT.

A Ponderosa Pine 8" dia. bears S45°W, 20 $\frac{1}{2}$  lks dist., mkd.  $\frac{1}{2}$  S21 BT.

Deposit corner stone alongside iron post.