

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established in 1881 by Herman D. Gradon, Under General Land Office Contract No. 416. Surveyor Generals Notes State: Top of ridge about 100 ft. high courses SE. Set a basalt stone 12x10x6 ins. 8" in the ground for $\frac{1}{4}$ sec. cor. marked $\frac{1}{4}$ on W face, dug pits 18x18x12ins. N and S of stone $5\frac{1}{2}$ ft. dist. and raised a mound of earth $1\frac{1}{2}$ ft. high $3\frac{1}{2}$ ft. base alongside.

DIAGRAM

T11S R37E
S32 $\frac{1}{4}$ S33
1983
PLS848

Description of corner evidence found:

Found a 12"x10"x7" stone with $\frac{1}{4}$ on W face. Set 6" in the ground in a old mound of stone and earth.
No bearing trees originally established, accepted position of the stone as $\frac{1}{4}$ corner.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 30"x2 $\frac{1}{2}$ " aluminum pipe with a 2 $\frac{1}{2}$ " aluminum cap stamped as shown in diagram. Set 18" in the ground, set original stone West alongside pipe and placed a ring of stone around the pipe.

From which:

No trees available, therefor set steel posts with warning and bearing tree signs as follows:
A Post bears East 3.0 ft.
A Post bears West 3.2 ft.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Corner monumented 9-2-83

OREGON
JULY 15, 1983
DOUGLAS M. FERGUSON
EAB

Witnessed by D. Mitchell Ferguson

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Nov 17, 1983

BAKER COUNTY SURVEYOR

SURVEY NO. 11-37-51

☆ GPO-798-276