


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T-11

History of original corner establishment:

N/A



Description of corner evidence found:

N/A

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2½"x30" alum. pipe with a 2½" alum. cap 24" in ground.
Stamped:

T11S R37E
C 1/4
S28
1995
LS 896

Marked:

8" D-Fir N84½W--12.2' Scribed XBT.

8" D-Fir S3W--6.8' Scribed C 1/4 S28 BT.

Set reference monuments, 5/8"x30" iron rods with 2" alum. caps:


(1) N45½W--16.9' Stamped: RM C 1/4 S28, 1995, LS 896, S45½E--16.9'.

(2) S67½E--14.7' Stamped: RM C 1/4 S28, 1995, LS 896, N67½W--14.7'


Nailed 54-9 and 54-3 signs to BT's, painted bands and blazes red and nailed a 1" brass disk stamped PLS 896 flush between the B and T.

Set guard posts North and East with 54-2 signs, one with 54-9 sign.

Bearings are magnetic--Declination 20°



Larry D. Bishop



Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED FEB. 4, 1998

BAKER COUNTY SURVEYOR

SURVEY NO. 11-37-111

*GPO-591-971, 1988