


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Y-20

History of original corner establishment:

N/A



Description of corner evidence found:

N/A

Description of monument and accessories I established to perpetuate the original location of this corner:

T11S R37E
SE 1/16
S35
1995
LS 896

Set: 2½"x30" alum. pipe with a 3" alum. cap 10" in ground in a mound of stone and earth 4½' base to top. Stamped:

Marked:


12" Ponderosa Pine N47¼W--9.4' Scribed SE 1/16 S35 BT. ---

12" Ponderosa Pine N74½E--17.4' Scribed XBT.


Nailed 54-9 and 54-3 signs to BT's, painted bands and blazes red and nailed a 1" brass disk stamped PLS 896 flush between the B and T.

Set guard post West with 54-2 and 54-9 signs.

Bearings are true by instrument tie.



Larry D. Bishop



Expires 12/31/95

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED FEB. 4, 1998
BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-140