

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Eugene P. McCornack, U.S. Deputy Surveyor
July 1881

67.30 Intersect second standard parallel south at a point 5.13 chains east of standard cor. to Tps. 10S. Rs. 37 and 38 E. at which point I set a post 4½ ft. long, 4 ins. square, 24 ins. in the ground for closing cor. to Tps. 11S. R 37 and 38 E.

C.C. T11S on S.,
R38E S6 on E.,
R37E S1 on W. faces, with 6 notches on S., E, and W. faces.

From which:

A fir, 24 ins. diam., bears N.40°E., 67 lks. dist. mkd. T10SR38ES31BT.
A pine, 36 ins. diam., bears S.40°E., 21 lks. dist. mkd. T11SR38ES6BT.
A tamarack, 12 ins. diam., bears S.70°W., 103 lks. dist. mkd. T11SR37ES1BT.

DIAGRAM

T 10 S R 38 E
S 31

S 1 | S 6
C C
R 37 E R 38 E
T 11 S
RLS 1060
1997

Owen C. Chatters II and Peter A. Peterson, Cadastral Surveyors
March 3, 1977

The closing cor. of Tps. 11S., Rs.37 and 38 E., determined at record bearing and distance from the remains of the original bearing trees:

A root hole, bears N.40°E., 67 lks. dist..
A pine stump, 36 ins. diam., bears S.40°E., 21 lks. dist., with scribe marks BT visible on open blaze..
A larch stump, 14 ins. diam., bears S.70°W., 103 lks. dist., with scribe marks BT visible on open blaze.

At the corner point:

Set an iron post, 28 ins. long, 2 ½ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

A fir, 11 ins. diam., bears S.72°E., 53 lks. dist. mkd. T11SR38ES6CCBT.
A fir, 9 ins. diam., bears S.82°W., 89 lks. dist. mkd. T11SR37ES1CCBT.

Bury a basalt stone, 9x7x2 ins., mkd. X, alongside iron post.

Description of corner evidence found:

Found a 2½" BLM brass cap, 2" out of the ground, with a stone mound to the cap.
From which:

A fir, 16" in diam., bears S.85°E., 35.5 ft., with healed blaze.
A fir, 15" in diam., bears S.83°W., 59.4 ft., with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

At true closing corner position, set a USFS 3¼" x 30" aluminum capped monument, with a magnet, 28" into the ground with a mound of stone to cap, marked as per diagram. Marked the original closing corner "AM" and obscured the monument.

From which:

A fir, 15" in diam., bears N.62°E., 36.7 ft., double blazed and scribed, "AUXBT" with nail and brass washer "RLS 1060" in face of BT.
A tamarack, 6" in diam., bears N.80°W., 17.5 ft., double blazed and scribed, "XBT" with nail and brass washer "RLS 1060" in face of BT.
The original closing corner bears S.0°21'41"W., 2.52 ft.

Placed Forest Service signs (54-2,54-9) on trees and paint scars, blazes, and 6" red band around all BT's.
Place a post with Forest Service Sign (54-9) alongside corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 2/98

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)

FILED *May 29, 1998*
BAKER COUNTY SURVEYOR
SURVEY NO. *11-37-147*
10-38-121
11-38-110