

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Eugene P. McCornack, U.S. Deputy Surveyor
July 27, 1881

40.00 Set a post 3 ft. long, 3 ins. square, 24 ins. in the ground for ¼ sec. cor., marked with ¼S on W. face. From which:

A fir, 16 ins. diam., bears N.55°E., 4 lks. dist. mkd. ¼SBT.
A pine, 24 ins. diam., bears S.50°W., 14 lks. dist. mkd. ¼SBT.

DIAGRAM

T 11 S
R 37 E R 38 E
¼
S 1 | S 6
|
RLS 1060
1997

Description of corner evidence found:

Did not find the monument or any of the bearing trees. This area has been logged and a lot of ground disturbances from the skidders.

Description of monument and accessories I established to perpetuate the original location of this corner:

At proportionate position, set a USFS 3¼" x 30" aluminum capped monument, with a magnet, 28" into the ground with a mound of stone to cap, marked as per diagram.

From which:

A tamarack, 19" in diam., bears N.37°50'E., 40.9 ft., double blazed and scribed, "¼S6BT" with nail and brass washer "RLS 1060" in face of BT.
A fir, 9" in diam., bears S.34°50'E., 20.1 ft., double blazed and scribed, "¼S6XBT" with nail and brass washer "RLS 1060" in face of BT.
A fir, 13" in diam., bears S.35°W., 31.5 ft., double blazed and scribed, "¼S1BT" with nail and brass washer "RLS 1060" in face of BT.
A tamarack, 15" in diam., bears N.26°W., 50.6 ft., double blazed and scribed, "¼S1XBT" with nail and brass washer "RLS 1060" in face of BT.

Placed Forest Service signs (54-2,54-9) on trees and paint scars, blazes, and 6" red band around all BT's.
Place a post with Forest Service Sign.(54-9) alongside corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 2/78

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19__

(COUNTY OFFICIAL) (DEPUTY)

C-1

FILED May 29, 1998
BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-148
11-38-117