

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
August 19, 1881

80.84 Intersect the W. boundary, 8 lks. S. of the cor. to secs. 6, 7, 1 + 12, which is a post 4 ins square, marked T11S S6 on N.E.
R38E S7 on S.E.
R37E S12 on S.W. and
S1 on N.W. faces, with 5 notches on S. and 1 notches on N. edges.

From which:

A pine, 30 ins. diam., bears N.55°E., 43 lks. dist. mkd. T11SR38ES6BT.
A pine, 24 ins. diam., bears S.35°E., 14 lks. dist. mkd. T11SR38ES7BT.
A pine, 18 ins. diam., bears S.75°W., 54 lks. dist. mkd. T11SR37ES12BT.
A tamarack, 20 ins. diam., bears N.25°W., 75 lks. dist. mkd. T11SR37ES1BT.

DIAGRAM
T 11 S
R 37 E R 38 E
S 1 | S 6
S 12 | S 7
1971

Owen C. Chatters II and James J. Carlson, Cadastral Surveyors
June 15, 1971

The cor. of secs. 1, 6, 7, 12, determined at record bearing and distance from the remains of the original bearing trees:

A pine stump, 36 ins. diam., bears N.55°E., 43 lks. dist. with scribe marks S6BT visible on open blaze.
A pine stump, 30 ins. diam., bears S.35°E., 43 lks. dist. with scribe marks BT visible on open blaze.
A pine stump, 22 ins. diam., bears S.75°W., 54 lks. dist., no marks visible.
A larch stump, 22 ins. diam., bears N.25°W., 75 lks. dist. with scribe marks S1BT visible on open blaze..

At the corner point:

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

A fir, 9 ins. diam., bears N.46°E., 24 lks. dist. mkd. T11SR38ES6BT.
A ponderosa pine, 12 ins. diam., bears S.5°E., 35 lks. dist. mkd. T11SR38ES7BT.
A ponderosa pine, 10 ins. diam., bears S.24°W., 109 lks. dist. mkd. T11SR37ES123BT.
A larch, 8 ins. diam., bears N.36°W., 87 lks. dist. mkd. T11SR37ES1BT.

The corner is located 29 lks. East of a wire fence extending N. and S.

Bury a basalt stone, 9x7x4 ins., mkd. X, on W. face alongside iron post.

Description of corner evidence found:

Found a 2 1/2" BLM brass cap, 2" out of the ground, with no stone mound to the cap, marked as per diagram.

From which:

A tamarack, 11" in diam., bears N.41°W., 57.2 ft., with healed blaze.
A fir, 10" in diam., bears N.40 1/2°E., 16.1', with healed blaze.
A pine, 14" in diam., bears S.10 1/2°E., 22.6', with healed blaze.
A pine, 13" in diam., bears S.20°W., 72.5', with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

Placed Forest Service signs (54-2, 54-9) on trees and paint scars, blazes and a 6" red band around BT's.
Placed two steel fence posts three to five feet from corner near property line with Forest Service signs (54-2).

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 2/98

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____

(COUNTY OFFICIAL) (DEPUTY)

FILED May 29, 1998
BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-149
11-38-128