

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

William R. Gradon, U.S. Deputy Surveyor
August 19, 1881

80.97 Intersect the W. boundary, 60 lks. S. of the cor. to secs. 7, 18, 12 + 13, which is a post 4 ins square, marked T11S S7 on N.E.

R38E S18 on S.E.

R37E S13 on S.W. and

S12 on N.W. faces, with 4 notches on S. and 2 notches on N.

edges; from which:

A pine, 30 ins. diam., bears N.30°E., 16 lks. dist. mkd. T11SR38ES7BT.

A pine, 16 ins. diam., bears S.20°E., 38 lks. dist. mkd. T11SR38ES18BT.

A tamarack, 18 ins. diam., bears S.80°W., 23 lks. dist. mkd. T11SR37ES13BT.

A tamarack, 24 ins. diam., bears N.70°W., 20 lks. dist. mkd. T11SR37ES7BT.

DIAGRAM
T 11 S
R 37 E R 38 E
S 12 | S 7
S 13 | S 18
1971

Owen C. Chatters II and Peter A. Peterson, Cadastral Surveyors
March 3, 1977

The cor. of secs. 7, 12, 13 and 18, monumented with the original corner post, 2 ins square, 4 ft. long, firmly set projecting 40 ins. above ground and in a small mound of stones, mkd. with illegible scribe marks on all four faces, from which the remains of the original bearing trees:

A root hole, bears N.30°E., 16 lks. dist. with a down and decayed pine alongside, 32 ins. diam., no marks visible.

A pine, 20 ins. diam., bears S.20°E., 38 lks. dist. with scribe marks T11SR38ES18BT visible on open blaze.

A larch snag, 20 ins. diam., bears S.80°W., 23 lks. dist. with scribe marks T11SR37ES13BT visible on open blaze.

A larch snag, 28 ins. diam., bears N.78°W., 20 lks. dist. with scribe marks T11SR37ES12BT visible on open blaze.

At the corner point:

Set an iron post, 28 ins. long, 2 ½ ins. diam., 24 ins. in the ground, with brass cap, from which new bearing trees:

A fir, 8 ins. diam., bears N.58°E., 25 lks. dist. mkd. T11SR38ES7BT.

A grand fir, 6 ins. diam., bears S.31°E., 18 ½ lks. dist. mkd. T11SR38ES18BT.

A larch, 6 ins. diam., bears S.32°W., 85 lks. dist. mkd. T11SR37ES13BT.

A grand fir, 15 ins. diam., bears N.28°W., 47 lks. dist. mkd. T11SR37ES7BT.

Deposit the original corner post and bury a basalt stone, 12x10x10 ins., mkd. X, on W. face alongside iron post.

Description of corner evidence found:

Found a 2 ½ ins. diam. BLM brass cap, 0.3' above the ground, in a small mound of stone to N., from which:

A fir, 7" in diam., bears N.45°E., 16.5', with healed blaze.

A fir, 9" in diam., bears S.29°E., 11.5', with healed blaze.

A pine, 18" in diam., bears S.18°E., 25.1', with visible marks on a partly healed blaze.

A tamarack, 7" in diam., bears S.30°W., 55.8', with healed blaze.

A fir, 17" in diam., bears N.28°W., 31.6', with healed blaze.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 2/98

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Description of monument and accessories I established to perpetuate the original location of this corner:

Placed Forest Service signs (54-2, 54-9) on trees and paint scars, blazes and a 6" red band around BT's.

Placed two steel fence posts three to five feet from corner near property line with Forest Service signs (54-2).

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19____
by _____
(COUNTY OFFICIAL) (DEPUTY)

FILED *May 29, 1998*

BAKER COUNTY SURVEYOR

SURVEY NO. *11-37-151*

11-38-135