

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Herman D. Gradon, U.S. Deputy Surveyor
August 19, 1881

81.10 Intersect the W. boundary, 34 lks. S. of the cor. to secs. 19, 30, 24 + 25, which is a stone 18x8x5 ins., marked with 2 notches on S. and 4 notches on N. edges.
From which:

A pine, 36 ins. diam., bears N.50°E., 67 lks. dist. mkd. T11SR38ES19BT.
A pine, 24 ins. diam., bears S.40°E., 16 lks. dist. mkd. T11SR38ES30BT.
A pine, 14 ins. diam., bears S.45°W., 75 lks. dist. mkd. T11SR37ES25BT.
A pine, 30 ins. diam., bears N.45°W., 16 lks. dist. mkd. T11SR37ES24BT.

DIAGRAM
T 11 S
R 37 E R 38 E
S 24 | S 19
S 25 | S 30
1972

Owen C. Chatters II and James J. Carlson, Cadastral Surveyors
June 15, 1971

The cor. of secs. 19, 24, 25, and 30, monumented with the original basalt stone, 18x8x5 ins., firmly set 6 ins. in the ground, mkd. with 2 grooves on the S. face and 4 grooves on the N. face from which the remains of the original bearing trees:

A root hole, bears N.50°E., 67 lks. dist.
A pine, 30 ins. diam., bears S.40°E., 18 lks. dist., with healed double blaze. (Record, 16 lks.).
A sawed pine stump, 20 ins. diam., bears S.45°W., 75 lks. dist., with fragmentary scribe marks visible on open blaze.
A pine, 25 ins. diam., bears N.45°W., 18 lks. dist., with fragmentary scribe marks visible on open blaze. (Record, 16 lks.)

At the corner point:

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 20 ins. in the ground, in a mound of stone, 2 1/2 ft. base, to top, with brass cap, from which new bearing trees:

A fir, 12 ins. diam., bears N.67°E., 27 lks. dist. mkd. T11SR38ES19BT.
A fir, 9 ins. diam., bears S.23°W., 72 lks. dist. mkd. T11SR38ES25BT.

Deposit the corner stone alongside iron post.

Description of corner evidence found:

Found a 2 1/2" BLM brass cap, 3" out of the ground, with a stone mound to the cap, marked as per diagram.

From which:

A fir, 17" in diam., bears N.65°30'E., 23.9 ft., with healed blaze.
A pine, 29" in diam., bears S.39°50'E., 11.4 ft., with healed blaze.
A fir, 18" in diam., bears S.22°20'W., 47.7 ft., with healed blaze.
A pine, 29" in diam., bears N.45°W., 11.4 ft., with visible scribe marks.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 2/98

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Description of monument and accessories I established to perpetuate the original location of this corner:

Placed Forest Service signs (54-2,54-9) on trees and paint scars, blazes and a 6" red band around BT's.
Place a post with Forest Service Sign (54-9) alongside corner.

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)

R-1

FILED May 29, 1998
BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-152
11-38-158