

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Eugene P. McCornack, U.S. Deputy Surveyor
1881

40.00 Set a basalt stone, 26x12x5 ins., 18 ins. in the ground for ¼ sec. cor., marked ¼
on W. face, From which:

A pine, 16 ins. diam., bears East, 36 lks. dist. mkd. ¼SBT.
A fir, 22 ins. diam., bears S.60°W., 10 lks. dist. mkd. ¼SBT.

DIAGRAM

T 11 S
R 37 E R 38 E
¼
S 25 | S 30

1972

Owen C. Chatters II and James J. Carlson, Cadastral Surveyors
June 15, 1971

The ¼ sec. cor. of secs. 25 and 30, monumented with the original basalt stone, 26x12x5 ins. firmly set 8 ins. in the ground, mkd. ¼ on W. face, from which the remains of the original bearing trees:

A pine, 18 ins. diam., bears S.77°E., 38 lks. dist., with fragmentary scribe marks visible on partially open blaze..
(Record, East, 36 lks.)
A fir snag, 22 ins. diam., bears S.60°W., 10 lks. dist., with healed double blaze.

Set an iron post, 28 ins. long, 2 ½ ins. diam., 14 ins. in the ground, to solid rock, and in a mound of stone, 3½ ft. base, to top, with brass cap,

from which new bearing tree:

A mahogany, 7 ins. diam., bears N.10°W., 61 lks. dist. mkd. ¼S25BT.

Deposit the corner stone alongside iron post.

Description of corner evidence found:

Found a 2½" BLM brass cap, 6" out of the ground, with a stone mound to the cap, marked as per diagram.

From which:

A stump, 19" in diam., bears S.77°20'E., 25.3 ft., with healed blaze.
A mahogany, 11 " in diam., bears N.10°W., 39.8 ft., with visible scribe marks.

Description of monument and accessories I established to perpetuate the original location of this corner:

A fir, 9" in diam., bears N.75°30'E., 49.3 ft., double blazed and scribed," XBT" with nail and brass washer "RLS 1060" in face of BT.
A juniper, 12" in diam., bears South, 52.9 ft., double blazed and scribed," ¼S30BT" with nail and brass washer "RLS 1060" in face of BT.
A juniper, 16" in diam., bears N.88°W., 30.0 ft., double blazed and scribed," ¼S25BT" with nail and brass washer "RLS 1060" in face of BT.

Placed Forest Service signs (54-2,54-9) on trees and paint scars, blazes and a 6" red band around BT's.
Place a post with Forest Service Sign (54-9) alongside corner.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

R. David Schurian 2/98

OREGON
JUNE 18, 1976
R. DAVID SCHURIAN
1060

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed in this office
for record on the ____ day of _____, 19 ____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)

FILED May 29, 1998
BAKER COUNTY SURVEYOR
SURVEY NO. 11-37-153
11-38-173