

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

NOT PREVIOUSLY ESTABLISHED.

P-24

DIAGRAM

T11S R38E
E 1/16
C ——— C
S24
PLS 91693
2022

DESCRIPTION OF CORNER EVIDENCE FOUND:

NONE, NOT PREVIOUSLY ESTABLISHED.

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

SET STANDARD USFS 2½"x30" ALUMINUM PIPE WITH ¾" ALUMINUM CAP, 12" IN THE GROUND IN A MOUND OF STONE WITH 2FT. BASE, 10" TALL AND PLACED A GRAY MAGNET AT THE BASE OF MONUMENT. CAP IS MARKED AS SHOWN IN DIAGRAM.

NEW ACCESSORIES:

A 5/8"x24" IRON ROD WITH 2" ALUMINUM CAP, BEARS N68°E, 7.85FT., STAMPED "RM 1", "2022", "PLS 91693", PROJECTING 1" ABOVE GROUND.

7" DIA. JUNIPER, BEARS N29°W, 5.23FT., SCRIBED "CE 1/16 S24 BT" WITH A 40D SPIKE IN THE RIGHT SIDE CENTER, APPROXIMATELY 1FT. ABOVE ROOT CROWN.

BEARING TREES HAVE A ¾" BRASS WASHERS STAMPED "PLS 91693" NAILED BETWEEN THE SCRIBED "B & T". BEARINGS WERE TAKEN FROM A MAGNETIC COMPASS WITH 14°E. DECLINATION. DISTANCES WERE MEASURED WITH A STEEL TAPE.

INSTALLED ALUMINUM GUARD POSTS WITH 54-2 & 54-9 SIGNS, 5FT. NORTH & 10FT. WEST OF MONUMENT.

DATE: SEPTEMBER 20, 2022
WITNESSES: T. DEJESUS QUINONES
VINCENT KELLY

FILED December 14, 2022
BAKER COUNTY SURVEYOR
SURVEY NO. 11-38-194

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert C. Moyers
OREGON
SEPTEMBER 11, 2018
ROBERT C. MOYERS
91693

RENEWS: 12/31/2022