

MONUMENTATION AND MAINTENANCE

See standard U.S.F.S. "INDEX No." in the circle on the map. Monuments are stamped as shown below. On each Bearing tree, nailed a brass washer stamped "PLS 848" blaze above the BT scribe and nailed warning signs on the back. Set steel posts with warning and boundary signs, on line within 5 ft. of property corners, or a single post with a warning sign within 5 ft. of controlling corners.

See "CERTIFIED RECORD OF LAND CORNER MONUMENTATION" forms on file in the office of the Baker County Surveyor for a complete history, description of evidence found, monument set, and accessories established at all corners set or maintained.

- (R-15) T11S R39E S22 1/4 --- Ponderosa Pine, 12' in dia, bears N82°30'W, 14.9 ft, scribed 1/4 S22 BT Ponderosa Pine, 12' in dia, bears S09°30'E, 7.0 ft, scribed 1/4 S27 BT 1972 (BLM CAP)
(R-19) T11S R39E S 23 1/4 --- Ponderosa Pine, 12' in dia, bears N59°15'E, 19.0 ft, scribed 1/4 S23 BT Ponderosa Pine, 14' in dia, bears S45°15'E, 9.5 ft, scribed 1/4 S26 BT 1970 (BLM CAP)
(S-13) T11S R39E N 1/16 S28 S27 Western Larch, 10' in dia, bears N83°52'W, 69.1 ft, scribed N1/16 S28 BT Western Larch, 18' in dia, bears N49°35'E, 47.9 ft, scribed N1/16 S27 BT 1991 PLS 848
(S-15) T11S R39E N 1/16 S27 Western Larch, 8' in dia, bears N22°30'E, 16.4 ft, scribed C-N 1/16 S27 BT Western Larch, 12' in dia, bears S03°45'E, 23.6 ft, scribed C-N 1/16 S27 BT 1991 PLS 848
(S-16) T11S R39E NE 1/16 White Fir, 10' in dia, bears N21°41'W, 3.4 ft, scribed NE 1/16 S27 BT Doug. Fir, 12' in dia, bears S36°52'W, 55.0 ft, scribed NE 1/16 S27 BT 1991 PLS 848
(S-17.5) T11S R39E C-W-NW 1/64 Western Larch, 12' dia, bears N55°44'W, 64.3 ft, scribed C-W-NW 1/64 S26 BT Ponderosa Pine, 14' dia, bears N68°13'E, 20.6 ft, scribed C-W-NW 1/64 S26 BT 1991 PLS 848
(S-18) T11S R39E NW 1/16 Western Larch, 10' in dia, bears N19°51'E, 32.3 ft, scribed NW 1/16 S28 BT Red Fir, 26' in dia, bears S69°09'W, 22.6 ft, scribed NW 1/16 S26 BT 1991 PLS 848
(T-13) T11S R39E 1/4 S28 S27 Ponderosa Pine, 10' in dia, bears S60°30'E, 25.0 ft, scribed 1/4 S27 BT Ponderosa Pine, 10' in dia, bears S51°15'E, 50.9 ft, scribed 1/4 S28 BT 1970 (BLM CAP)
(T-15) T11S R39E C 1/4 Ponderosa Pine, 16' dia, bears N24°04'W, 135.8 ft, scribed C1/4 S27 BT Ponderosa Pine, 16' dia, bears N00°28'E, 133.7 ft, scribed C1/4 S27 BT Juniper, 10' dia, bears S55°39'E, 111.6 ft, scribed C1/4 S27 BT Ponderosa Pine, 20' dia, bears S06°52'E, 95.3 ft, scribed C1/4 S27 BT 1991 PLS 848
(T-16) T11S R39E E 1/16 White Fir, 10' in dia, bears N09°21'E, 31.1 ft, scribed C-E 1/16 S27 BT White Fir, 8' in dia, bears S68°22'E, 24.7 ft, scribed C-E 1/16 S27 BT 1991 PLS 848
(T-17.5) T11S R39E C-W-W 1/64 Red Fir, 10' in dia, bears N81°17'E, 48.9 ft, scribed C-W-W 1/64 S26 BT W. Larch, 10' in dia, bears S74°00'W, 24.1 ft, scribed C-W-W 1/64 S26 BT 1991 PLS 848
(T-18) T11S R39E W 1/16 C Western Larch, 10' dia, bears N87°27'E, 35.9 ft, scribed C-W 1/16 S26 BT White Fir, 12' dia, bears S64°55'W, 27.2 ft, scribed C-W 1/16 S26 BT 1991 PLS 848
(T-19) T11S R39E C1/4 Ponderosa Pine, 10' dia, bears N72°03'W, 46.3 ft, scribed C1/4 S26 BT Ponderosa Pine, 12' dia, bears N14°35'E, 45.0 ft, scribed C1/4 S26 BT Ponderosa Pine, 14' dia, bears N81°30'E, 18.1 ft, scribed C1/4 S26 BT Western Larch, 12' dia, bears S35°11'W, 101.7 ft, scribed C1/4 S26 BT 1991 PLS 848
(U-17) T11S R39E S 1/16 S27 S26 Western Larch, 8' dia, bears N59°40'W, 63.9 ft, scribed S1/16 S27 BT White Fir, 14' dia, bears N40°34'E, 9.8 ft, scribed S1/16 S26 BT 1991 PLS 848
(U-19) T11S R39E S1/16 S26 Ponderosa Pine, 14' dia, bears S55°04'E, 35.5 ft, scribed C-S 1/16 S26 BT Western Larch, 16' dia, bears S41°40'W, 105.5 ft, scribed C-S 1/16 S26 BT 1991 PLS 848

- (V-11) T11S R39E S 28 1/4 --- A Juniper, 10' in dia, bears S24°45'W, 43.8 ft, scribed 1/4 S33 BT 1972 (BLM CAP)
(V-15) T11S R39E S 27 1/4 --- A Mtn. Mahogany, 10' dia, bears N50°07'W, 64.5 ft, scribed 1/4 S27 BT A Mtn. Mahogany, 10' dia, bears N15°32'E, 100.4 ft, scribed 1/4 S27 BT Ponderosa Pine, 8' dia, bears S64°24'E, 35.5 ft, scribed 1/4 S34 BT A Mtn. Mahogany, 8' dia, bears S 3°34'E, 10.6 ft, scribed 1/4 S34 BT 1991 PLS 848
(V-17) T11S R39E S27 S26 A 5/8" x 30" rebar, set 28" in the ground, with yellow plastic cap marked PLS 848 bears: N45°W, 21.4 ft. (no grooves on rebar) S34 S35 N45°E, 11.5 ft. (1 groove on rebar) S45°E, 9.8 ft. (2 grooves on rebar) S45°W, 29.5 ft. (3 grooves on rebar) 1991 PLS 848
(V-18) T11S R39E S 26 W1/16 --- A 5/8" x 30" rebar, set 28" in the ground, with yellow plastic cap marked PLS 848 bears: N41°20'W, 15.2 ft. (no groove on rebar) S35 N37°04'E, 13.6 ft. (1 groove on rebar) S27°55'E, 15.4 ft. (2 grooves on rebar) S48°06'W, 13.5 ft. (3 grooves on rebar) 1991 PLS 848
(V-19) T11S R39E S 26 1/4 --- 5/8" x 30" rebar, set 28" in the ground, with yellow plastic cap marked PLS 848 bears: N80°54'W, 13.5 ft. (no groove on rebar) S35 N57°19'E, 13.9 ft. (1 groove on rebar) S37°36'E, 20.4 ft. (2 grooves on rebar) S29°36'W, 20.5 ft. (3 grooves on rebar) 1991 PLS 848
(V-21) T11S R39E S26 S25 Alpine Fir, 8' dia, bears S28°15'W, 121.9 ft, scribed T11S R39E S35 BT A 5/8" x 30" rebar pin, set 28" in the ground, with a yellow plastic cap marked PLS 848 bears N45°W, 8.0 ft. 1970 (BLM CAP)
(W-11.5) T11S R39E C-W-NE 1/64 Ponderosa Pine, 14' dia, bears S33°03'E, 47.9 ft, scribed C-W-NE 1/64 S33 BT Ponderosa Pine, 10' dia, bears S27°10'W, 55.9 ft, scribed C-W-NE 1/64 S33 BT 1991 PLS 848
(W-13) T11S R39E N 1/16 Red Fir, 10' dia, bears S67°10'E, 9.5 ft, scribed N1/16 S34 BT Ponderosa Pine, 12' dia, bears S12°46'W, 28.6 ft, scribed N1/16 S33 BT 1991 PLS 848
(X-9) T11S R39E 1/4 Juniper, 10' dia, bears S38°30'W, 55.6 ft, scribed 1/4 S32 BT Juniper, 8' dia, bears N54°30'E, 24.5 ft, scribed 1/4 S33 BT 1972 (BLM CAP)
(X-11) T11S R39E C1/4 Ponderosa Pine, 10' dia, bears N42°35'W, 23.7 ft, scribed C1/4 S33 BT Ponderosa Pine, 12' dia, bears N49°10'E, 13.4 ft, scribed C1/4 S33 BT Ponderosa Pine, 8' dia, bears S50°29'W, 27.1 ft, scribed C1/4 S33 BT Ponderosa Pine, 9' dia, bears N 8°51'W, 29.5 ft, scribed C1/4 S33 BT 1991 PLS 848
(X-11.5) T11S R39E C-W-E 1/64 Ponderosa Pine, 10' dia, bears S63°00'E, 19.2 ft, scribed C-W-E 1/64 S33 BT Ponderosa Pine, 8' dia, bears S37°30'W, 26.4 ft, scribed C-W-E 1/64 S33 BT 1991 PLS 848
(X-12) T11S R39E E1/16 C Ponderosa Pine, 10' dia, bears S58°35'W, 48.6 ft, scribed C-E 1/16 S33 BT Ponderosa Pine, 12' dia, bears S23°03'W, 39.3 ft, scribed C-E 1/16 S33 BT 1991 PLS 848
(X-13) T11S R39E 1/4 Douglas Fir, 16' dia, bears N14°49'W, 47.7 ft, scribed 1/4 S33 BT Ponderosa Pine, 14' dia, bears N78°42'E, 17.5 ft, scribed 1/4 S34 BT Douglas Fir, 16' dia, bears S13°47'E, 41.9 ft, scribed 1/4 S34 BT Douglas Fir, 10' dia, bears S72°16'W, 17.7 ft, scribed 1/4 S33 BT 1970 (BLM CAP)
(X-15) T11S R39E C 1/4 Douglas Fir, 16' dia, bears N62°07'W, 82.2 ft, scribed C1/4 S34 BT White Fir, 10' dia, bears N20°38'E, 54.8 ft, scribed C1/4 S34 BT White Fir, 14' dia, bears N68°05'E, 72.6 ft, scribed C1/4 S34 BT Ponderosa Pine, 14' dia, bears S78°09'E, 78.3 ft, scribed C1/4 S34 BT 1991 PLS 848

- (X-17) T11S R39E 1/4 S34 S35 Juniper, 12' dia, bears N84°55'W, 26.1 ft, scribed 1/4 S34 BT Juniper, 10' dia, bears S70°49'E, 59.4 ft, scribed 1/4 S35 BT Juniper, 14' dia, bears S07°02'E, 65.6 ft, scribed 1/4 S35 BT 1991 PLS 848 Juniper, 10' dia, bears S10°30'W, 17.9 ft, scribed 1/4 S34 BT
(X-18) T11S R39E W1/16 C --- Juniper, 8' dia, bears S45°51'E, 38.8 ft, scribed C-W 1/16 S35 BT Juniper, 12' dia, bears S17°48'W, 33.1 ft, scribed C-W 1/16 S35 BT 1991 PLS 848
(X-19) T11S R39E C1/4 Ponderosa Pine, 16' dia, bears N22°34'W, 13.1 ft, scribed C1/4 S35 BT Juniper, 10' dia, bears N79°35'E, 20.9 ft, scribed C1/4 S35 BT Juniper, 12' dia, bears S06°00'E, 16.2 ft, scribed C1/4 S35 BT Ponderosa Pine, 14' dia, bears S52°39'W, 28.8 ft, scribed C1/4 S35 BT 1991 PLS 848
(X-20) T11S R39E E1/16 C --- Ponderosa Pine, 14' dia, bears N27°58'W, 53.5 ft, scribed C-E 1/16 S35 BT Juniper, 10' dia, bears N36°15'E, 39.8 ft, scribed C-E 1/16 S35 BT 1991 PLS 848
(X-21) T11S R39E 1/4 A 5/8" x 30" rebar, set 28" in the ground, with yellow plastic cap marked PLS 848 bears: N45°W, 9.9 ft. (no grooves) N45°E, 10.3 ft. (1 groove) 1986 DRLS 1639
(Y-13) T11S R39E S1/16 S33 S34 Ponderosa Pine, 12' dia, bears N64°17'W, 19.6 ft, scribed S1/16 S33 BT Ponderosa Pine, 14' dia, bears N06°06'E, 34.0 ft, scribed S1/16 S33 BT 1991 PLS 848
(Y-15) T11S R39E S1/16 S34 Ponderosa Pine, 12' dia, bears N69°50'W, 5.3 ft, scribed C-S 1/16 S34 BT Juniper, 7' dia, bears S03°15'W, 8.5 ft, scribed C-S 1/16 S34 BT 1991 PLS 848
(Y-19) T11S R39E S1/16 S35 Ponderosa Pine, 18' dia, bears S68°21'E, 22.7 ft, scribed C-S 1/16 S35 BT Douglas Fir, 25' dia, bears S22°49'W, 46.1 ft, scribed C-S 1/16 S35 BT 1991 PLS 848
(Y-20) T11S R39E SE 1/16 A 5/8" x 30" rebar, set 28" in the ground, with yellow plastic cap marked PLS 848 bears: N22°19'W, 8.9 ft. (No grooves) S52°54'W, 12.3 ft. (1 groove) 1991 PLS 848
(Z-11) T11S R39E S 33 1/4 Juniper, 9' dia, bears N56°15'W, 67.9 ft, scribed 1/4 S33 BT Ponderosa Pine, 6' dia, bears N54°30'E, 74.9 ft, scribed 1/4 S33 BT Ponderosa Pine, 18' dia, bears S30°45'E, 79.8 ft, scribed 1/4 S4 BT Juniper, 12' dia, bears S06°00'E, 73.8 ft, scribed 1/4 S4 BT 1991 PLS 848
(Z-12) T11S R39E S 33 E1/16 C Ponderosa Pine, 10' dia, bears S23°20'W, 33.0 ft, scribed E1/16 S4 BT Ponderosa Pine, 6' dia, bears N06°17'E, 34.7 ft, scribed E1/16 S33 BT 1991 PLS 848
(Z-17) T11S R39E S34 S35 Ponderosa Pine, 18' dia, bears N65°15'W, 37.0 ft, scribed T11S R39E S34 BT Ponderosa Pine, 16' dia, bears S18°45'E, 35.8 ft, scribed T11S R39E S 2 BT 1970 (BLM CAP)
(Z-19) T11S R39E S 35 1/4 Ponderosa Pine, 9' dia, bears N38°30'W, 26.5 ft, scribed 1/4 S35 BT Ponderosa Pine, 16' dia, bears S69°30'E, 54.1 ft, scribed 1/4 S2 BT 1970 (BLM CAP)

REGISTERED PROFESSIONAL LAND SURVEYOR DOUGLAS M. FERGUSON 848

FILED May 26, 1992 BAKER COUNTY SURVEYOR SURVEY NO. 11-39-110