

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. N-2

History of original corner establishment:

In 1960, C. Albert White, Cadastral Surveyor for The Bureau Of Land Managment, under special instructions, group No. 261, dated Sep. 3, 1940, approved Jan. 16, 1941, and assignment instructions dated May 5, 1960, set 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM from which:

DIAGRAM  
S18  
W1/16---  
S19  
T11S R41E  
1960  
(BLM CAP)



A Fir 12 ins. diam. bears N27E, 731ks dist mkd. W1/16 S18 BT  
A Pine 16 ins. diam. bears S50W, 411ks dist mkd. W1/16 S19 BT

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM. Corner monument is solid and in good condition. All previously established accessories have been rendered useless in the long term by the 1989 fire. Refer to the above referenced notes.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 1/2" x 24" iron pins with aluminum caps as follows:  
S12-07'W, 11.9 ft., stamped W1/16 S19, RM with an arrow and course to the corner.  
N89-21'E, 267.73 ft., stamped W1/16 S18, RM with an arrow and course to the corner. This pin is part of the survey control network. Set a steel post with warning sign along side this pin.  
Measurements to pin taken with electronic tachimeter with angles turned from the survey control network.  
Set steel posts with warning sign 5' North.



This work is performed by:  
Douglas M. Ferguson PLS 848  
D. Mitchell Ferguson & Ken H. Delano  
On June 8, 1990  
Refer to Baker Co. Survey No. 11-41 - 1

Office of \_\_\_\_\_ County of \_\_\_\_\_  
State of \_\_\_\_\_ I hereby certify that the within instrument was filed  
in this office for record on the \_\_\_\_\_ day of \_\_\_\_\_, 19\_\_\_\_  
by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan. 4, 1991  
BAKER COUNTY SURVEYOR  
SURVEY NO. 11-41-3