

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

INDEX No. 0-1

DIAGRAM
IN1/16
IS19
IT119
IR41E
1960
(BLM CAP)

History of original corner establishment:

In 1960, C. Albert White, Cadastral Surveyor for The Bureau Of Land Management, under special instructions, group No. 261, dated Sep. 3, 1940, approved Jan. 16, 1941, and assignment instructions dated May 5, 1960, set 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM from which:

- A Fir 10 ins. diam. bears N68E, 371ks dist mkd. N1/16 S19 BT
- A Fir 10 ins. diam. bears S35E, 641ks dist mkd. N1/16 S19 BT

Description of corner evidence found:

Found 2-1/2" iron pipe with 3" brass cap stamped as shown in the DIAGRAM. Corner monument is solid and in good condition. All previously established accessories have been rendered useless in the long term by the 1989 fire. Refer to the above referenced notes.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 1/2" x 24" iron pins with aluminum caps as follows:
S48-33'E, 12.2 ft., stamped N1/16, S19, RM with an arrow and course to the corner.
N33-53'E, 10.5 ft., stamped N1/16, S19, RM with an arrow and course to the corner.
Measurements to pin taken with electronic tachimeter with angles turned from the survey control network.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 12, 1903
DOUGLAS M. FERGUSON
848

This work is performed by:
Douglas M. Ferguson PLS 848
D. Mitchell Ferguson & Ken H. Delano
On June 6, 1990
Refer to Baker Co. Survey No. 11-41 -L

Office of _____ County of _____
State of _____ I hereby certify that the within instrument was filed
in this office for record on the _____ day of _____, 19____
by _____
(COUNTY OFFICIAL) (DEPUTY)

FILED Jan. 4, 1991
BAKER COUNTY SURVEYOR
NO. 11-41-5